

WILLEO TRAIL - PHASE IV

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS PROPOSED PEDESTRIAN TRAIL

CITY OF ROSWELL
FULTON COUNTY, GEORGIA

STATE	SHEET NO.	TOTAL SHEETS
GA	34	


50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE





24 HOUR ENGINEERING
CONTACT - STEVE ROWE
(770) 641-1942 WORK

AEC JOB # 09-2891.21
PROGRESS SET 03-05-10



MAYOR: JERE WOOD

COMMUNITY DEVELOPMENT - BETTY PRICE
TRANSPORTATION - RICH DIPPOLITO
PUBLIC WORKS/ ENVIRONMENTAL - BECKY WYNN
PUBLIC SAFETY - NANCY DIAMOND
RECREATION, PARKS, HISTORIC & CULTURAL AFFAIRS - KENT INGLEHEART
ADMINISTRATION AND FINANCE - JERRY ORLANS



LENGTH OF PROJECT
5,364.85 LF
1.02 MILES

NOTES:

- ALL WORK SHALL CONFORM TO "GDOT STANDARD SPECIFICATIONS - 2001 EDITION", AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION AND MODIFIED BY THE CONTRACT DOCUMENTS.
- REFERENCE PLANS BY JORDAN, JONES & GOULDING, DATED 05/07/2004 AND WOODALL & ASSOCIATES LAND SURVEYORS, INC., DATED 03/06/2009 AS BASE INFORMATION FOR THIS DRAWING.
- ALL REFERENCES IN THIS DOCUMENT, WHICH INCLUDE ALL PAPERS, WRITINGS, DOCUMENTS, DRAWINGS, OR PHOTOGRAPHS USED, OR TO BE USED IN CONNECTION WITH THIS DOCUMENT, TO "STATE HIGHWAY DEPARTMENT OF GEORGIA", "STATE HIGHWAY DEPARTMENT", "GEORGIA STATE HIGHWAY DEPARTMENT", "HIGHWAY DEPARTMENT", OR "DEPARTMENT" WHEN THE CONTEXT THEREOF MEANS THE STATE HIGHWAY DEPARTMENT OF GEORGIA MEAN, AND SHALL BE DEEMED TO MEAN THE DEPARTMENT OF TRANSPORTATION.
- THIS PROJECT HAS BEEN DESIGNED WITH THE TITLE II PROVISIONS OF THE AMERICANS WITH DISABILITIES ACT (ADA).
- NOTICE OF INTENT IS REQUIRED. SEE SHEET 35 FOR ADDITIONAL INFORMATION.

INDEX OF DRAWINGS	
SHEET	SHEET TITLE
34	EROSION, SEDIMENT AND POLLUTION CONTROL COVER
35-36	EROSION, SEDIMENTATION AND POLLUTION CONTROL NOTES
37	DRAINAGE AREA MAP
38-47	EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS
48-54	EROSION CONTROL DETAILS
55	WATERSHED PLAN

PLANS COMPLETED (DATE)	REVISIONS

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN (ESPCP)

General Note: All measures outlined in this plan are to be in accordance with the "Manual for Erosion and Sediment Control in Georgia," latest edition.

Project Name: Willeo Trail Phase IV
 Location: City of Roswell, Fulton County, Georgia
 BEGINNING: Latitude: N 34° 00' 24.09"
 Longitude: W 84° 22' 29.72"

I. Certifications

Owner / Operator Certification
 "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified persons properly gather and evaluate the information submitted. Based upon my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Owner / Operator's Printed Name: _____
 Title: _____

Signature: _____ Date: _____

Designer Certification
 "I certify that the Permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia" (Manual) published by the State Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the storm water outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the Georgia NPDES Permit No. GAR 100002."

Signature: *Mark Van De Water* Date: 3-10-10
 GSWCC Level II Certified Design Professional # 6960

"I certify under penalty of law that this Plan was prepared after a site visit to the locations described herein by myself or my authorized agent, under my direct supervision."

Signature: *Mark Van De Water* Date: 3-10-10
 GSWCC Level II Certified Design Professional # 6960

I CERTIFY THAT THE GEORGIA 2008 305(b)(3)(3)(d) LIST DOCUMENTS HAVE BEEN CONSULTED TO DETERMINE THE PROJECT SITE IS NOT WITHIN 1 LINEAR MILE UPSTREAM OR DOWNSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF AN BIOTA IMPAIRED STREAM SEGMENT.

Signature: *Mark Van De Water* DATE: 3-10-10
 MARK VAN DE WATER, PE
 GSWCC #: 0000006962
 EXPIRES: 03/11/2012

7-Day BMP Inspection by Design Professional

The below statement is to be signed by the Design Professional after construction has begun and initial BMPs have been installed and inspected.

The Design Professional was notified of on _____ that land disturbance activities had begun on the subject project. As required by the Georgia NPDES Permit No. GAR 100002, an inspection of the erosion control measures (BMPs) was conducted by the Design Professional on _____. A copy of the inspection letter can be obtained from the Owner or Design Professional.

Signature: _____ Date: _____

DEVELOPER
 CITY OF ROSWELL
 PARKS & RECREATION
 DEPARTMENT
 38 HILL STREET, SUITE 100
 ROSWELL, GA 30075
 CONTACT: JEFF PRUITT
 (770) 641-3705

ENGINEER
 AEC, INC.
 50 WARM SPRINGS CIRCLE
 ROSWELL, GEORGIA 30075
 CONTACT:
 MARK VAN DE WATER, P.E.
 (770) 641-1942

**EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST
 INFRASTRUCTURE CONSTRUCTION PROJECTS**


SWCD: _____
 Project Name: Willeo Trail Address: _____
 City/County: City of Roswell, Fulton County Date on Plans: 03-05-2010

Plan Included TO BE SHOWN ON ES&PC PLAN
 Page # Y/N

- 36 Y 1. The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted. (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed)
- 38-47 Y 2. Level II certification number issued by the Commission, signature and seal of the certified design professional. (Signature, seal and Level II number must be on each sheet pertaining to ES&PC plan or the Plan will not be reviewed)
- 38-47 Y 3. The name and phone number of the 24-hour local contact responsible for erosion, sedimentation and pollution controls.
- 36 Y 4. Provide name, address and phone number of primary permittee.
- 37 Y 5. Note total and disturbed acreage of the project or phase under construction.
- 1 Y 6. Provide land lot and district numbers for site location. Describe critical areas and any additional measures that will be utilized for these areas.
- 1 Y 7. Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.
- ALL Y 8. Graphic scale and north arrow.
- ALL Y 9. Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following:
 Existing Contours: USGS 1" : 2000' Topographical Sheets
 Proposed Contours: 1" : 400' Centerline Profile
- 37 Y 10. Delineation and acreage of contributing drainage basins on the project site.
- 38-47 Y 11. Delineation of on-site wetlands and all state waters located on and within 200 feet of the project site.
- 38-47 Y 12. Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to state waters and any additional buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.
- 55 Y 13. Delineate all sampling locations, perennial and intermittent streams and other water bodies into which storm water is discharged.
- N/A N 14. Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/Delineate all storm water discharge points.
- 36 Y 15. Soil series for the project site and their delineation.
- 35 Y 16. Identify the project receiving waters and describe all adjacent areas including streams, lakes, residential areas, wetlands, etc. which may be affected.
- N/A N 17. Any construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile upstream of and within the same watershed as, any portion of an Biota Impaired Stream Segment must comply with Part III, C. of the Permit. Include the completed Appendix 1 listing all the BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment.
- N/A N 18. If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in item 18 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan.
- 55 Y 19. Delineate on-site drainage and off-site watersheds using USGS 1" : 2000' topographical sheets.
- ALL Y 20. Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.
- 38-47 Y 21. The limits of disturbance for each phase of construction.
- 35 Y 22. Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been achieved. A written rationale explaining the decision to use equivalent controls when a sediment basin is not attainable must be included in the plan for each common drainage location in which a sediment basin is not provided. Worksheets from the Manual must be included for structural BMPs and all calculations used by the design professional to obtain the required sediment storage when using equivalent controls.
- N/A N 23. Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at www.gaswcc.org

- 38-47 Y 24. Best Management Practices to minimize off-site vehicle tracking of sediments and the generation of dust
- 35 Y 25. BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum at the construction site is prohibited.
- 35 Y 26. Provide BMPs for the remediation of all petroleum spills and leaks.
- 38-47 Y 27. Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.
- 35 Y 28. Description of the nature of construction activity.
- 35 Y 29. A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final BMPs.
- N/A N 30. Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
- 35 Y 31. Description of the practices that will be used to reduce the pollutants in storm water discharges.
- 35 Y 32. Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed.
- 36 Y 33. Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on page 15 of the permit.
- 36 Y 34. Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on page 14 of the permit.
- 36 Y 35. Certification statement and signature of the permittee or the duly authorized representative as stated in section V.G.2.d. of the state general permit.
- 35 Y 36. An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.
- 35 Y 37. Indication that non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measured from the point of wrested vegetation without first acquiring the necessary variances and permits.
- 36 Y 38. Indication that the design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation.
- 35 Y 39. Indication that amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional.
- 35 Y 40. Indication that waste materials shall not be discharged to waters of the State, except as authorized by a Section 404 permit.
- 35 Y 41. Documentation that the ES&PC Plan is in compliance with waste disposal, sanitary sewer, or septic tank regulations during and after construction activities have been completed.
- 35 Y 42. Provide complete requirements of inspections and record keeping by the primary permittee.
- 35 Y 43. Provide complete requirements of sampling frequency and reporting of sampling results.
- 35 Y 44. Provide complete details for retention of records as per Part IV.F. of the permit.
- 35 Y 45. Description of analytical methods to be used to collect and analyze the samples from each location.
- 35 Y 46. Appendix B rationale for outfall sampling points where applicable.
- 35 Y 47. Clearly note statement in bold letters: "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to, or concurrent with, land disturbing activities."
- 35 Y 48. Clearly note maintenance statement in bold letters - "Erosion control measures will be maintained at all times. If full implementation of the approved plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source."
- 35 Y 49. Clearly note the statement in bold letters - "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding."
- 48-54 Y 50. Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.
- 48-54 Y 51. Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of year that seeding will take place and for the appropriate geographic region of Georgia.

Effective January 1, 2010




SOILS DATA LEGEND	
SYMBOL	NAME
BaA	Buncombe Loamy Sand, 0-3% Slopes, Occasionally Flooded
CaA	Cartecay-Toccoa Complex, 0-2% Slopes, Occasionally Flooded
CeC2	Cecil Sandy Loam, 6-10% Slopes, Moderately Eroded
CpA	Congaree Sandy Loam, 0-2% Slopes, Occasionally Flooded
MdC2	Madison-Bethlehem Complex, 6-10% Slopes, Moderately Eroded
PaD2	Pacolet Sandy Loam, 10-15% Slopes, Moderately Eroded
ReD	Rion Sandy Loam, 10-15% Slopes
RoF	Rion-Louisburg Complex, 20-35% Slopes, Bouldery
W	Water
WbA	Wehadkee-Cartecay Complex, 0-2% Slopes, Occasionally Flooded

DATE	REVISIONS	DATE	REVISIONS

AEC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecat.com


LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE



EROSION, SEDIMENTATION AND POLLUTION CONTROL NOTES



**WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS**



NOTES:

TOTAL PROJECT AREA (ACRES): 2.60
 TOTAL DISTURBED AREA(ACRES): 2.60
 100 YEAR HEADWATER ELEVATION IS 863.

MONITORING LOCATIONS													
BASIN	TOTAL ACREAGE (Ac)	DISTURBED ACREAGE	AVERAGE SLOPE	PRE-DEVELOPED					POST-DEVELOPED				
				Q50	Q100	V50	V100	C	Q50	Q100	V50	V100	C
ROCK DAM C	0.06	0.02	11.60%	0.43	0.47	0.96	0.94	0.78	0.43	0.47	0.96	0.94	0.78
BRIDGE	2.64	0.26	0.80%	12.08	13.13	2.63	2.73	0.50	12.08	13.13	2.63	2.73	0.50
ROCK DAM E	0.13	0.03	9.40%	0.99	1.07	1.32	1.34	0.83	0.99	1.07	1.32	1.34	0.83
ROCK DAM F	0.05	0.02	10.50%	0.34	0.37	0.85	0.82	0.75	0.34	0.37	0.85	0.82	0.75




50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecat.com

LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE






DRAINAGE AREA MAP



DATE	REVISIONS	DATE	REVISIONS



WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS




A-EC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecat.com

LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE



EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS



WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS

1/20/2010 09:09:28 AM WILLEO TRAIL Concept Permitting 05-2881 PG 38 of 407 Plans.dwg, 3/5/2010 5:22:07 PM, mwk, kfp, 7000.dwg, 1:1




AEC

50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

REGISTERED PROFESSIONAL ENGINEER
NO. 027118
EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS

ROSWELL
GEORGIA
SINCE 1854

**WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS**

C:\2008\05\09\2891 WILLEO TRAIL Concept Permitting\052891 PE Gas-DOT plans.dwg, 3/5/2010 5:23:06 PM, mdy, Kip 7000, psd, 1:1




A-EC

50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

REGISTERED PROFESSIONAL ENGINEER
NO. 027118
GWSWCC #6980
EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS

ROSWELL
GEORGIA
SINCE 1854

WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

I:\2010\08\09\09-2891 WILLEO TRAIL Concept Permitting\05-2891 PE_Ga-DOT Plans.dwg, 3/5/2010 5:27:08 PM, mdc, Kip 7000.pcd, 1:1




A-EC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecat.com

LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE



GSWCC #8960
 Exp. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN



DATE	REVISIONS	DATE	REVISIONS

**WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS**




50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE



EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN



DATE	REVISIONS	DATE	REVISIONS




**WILLEO TRAIL - PHASE IV
ROSSELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS**

I:\2010\05\05-2881 WILLEO TRAIL Concept Permitting\05-2881 PG Co-DOT plans.dwg, 3/20/10 5:37:08 PM, mkr_kip_7000.pcl, 1:1

STATE	SHEET NO.	TOTAL SHEETS
GA	43	




SETTING)




A-EC

50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecatl.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE



EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS



**WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS**

A:\2006\08\09\2881 WILLEO TRAIL Concept\Permitting\08-2881 PR Ge-DOT plans.dwg, 3/5/2010 5:38:58 PM, mck, Kp 7000.pct, 1:1




AEC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecat.com

LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE

GEORGIA
 REGISTERED PROFESSIONAL ENGINEER
 NO. 027118
 LAND

GSWCC #8960
 EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS

ROSWELL
 GEORGIA
 SINCE 1854

**WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS**

03/09/2010 09:28:11 WILLEO TRAIL Concept Permitting/05-2851 PG Ge-DOT Plans.dwg, 3/6/2010 5:40:27 PM, mdu, K07 7000.pcd, 1:1



AEC

50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com


LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

REGISTERED PROFESSIONAL ENGINEER

DAVID VANDEWEYER

GSWCC #9980
EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS

ROSWELL
GEORGIA
SINCE 1854

WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

2020/CJ/S09-2891 WILLEO TRAIL Concept Permitting/09-2891 PE Ge-DOT Plans.dwg, 3/5/2010 5:41:20 PM, mtr, kpr 7000.plt, 11


STATE	SHEET NO.	TOTAL SHEETS
GA	46	



AEC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecatl.com
 LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE

GEORGIA
 REGISTERED
 PROFESSIONAL
 LANDSCAPE ARCHITECT
 GSWCC #8960
 EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN





DATE	REVISIONS	DATE	REVISIONS

ROSWELL
 GEORGIA
 SINCE 1854

WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS

1/20/2010 09:59:29 AM WILLEO TRAIL Concept Planning/09-2991 PB Co-DOT plans.dwg, 3/5/2010 5:42:19 PM, mdc, klp, klp, 7000, psd, 1:1




AEC

50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

GSWCC #0980
EXP. 3-11-2012

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN



DATE	REVISIONS	DATE	REVISIONS

ROSWELL
GEORGIA
SINCE 1854

WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

C:\Users\joshua\Desktop\Willeo Trail\Concept\Permitting\09-28-11\Willeo Trail\Concept\Permitting\09-28-11\Fig GeDOT plans.dwg, 3/6/2010 5:43:14 PM, mdr, Kip 700, pcd, 1:1

CODE	PRACTICE STD. / SPC. / SECTION	DETAIL	DESCRIPTION
(S41-R)	CONSTRUCTION SECTION 163		THIS ITEM CONSISTS OF INTERMINGLED BRUSH, LOGS, ETC. SO AS NOT TO FORM A SOLID DAM. CONSTRUCTION OF THE BRUSH BARRIER SHOULD BE USED AT THE TOE OF FILL SLOPES ON GRADED AREAS IN URBAN AREAS WHERE SUFFICIENT HEIGHT OF BRUSH OR LOGS IS AVAILABLE TO FEET ON SLOPE. THE BARRIER SHOULD BE PLACED PERPENDICULAR TO THE FLOW OF WATER OR EASEMENT LIMITS. IT WILL NOT BE PLACED IN WETLANDS, WETLANDS OR OTHER AREAS WHERE THE CLEARANCE AND GRABBING COSTS. NO SEPARATE PAYMENT SHALL BE MADE.
(S41-R)	CONSTRUCTION SECTION 163		A BARRIER OF BAILED STRAW IS USED TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. IT IS USED ON SLOPES OF 1:1 TO 3:1. FILL HEIGHTS SHOULD NOT EXCEED 10 FEET. THE BAILED STRAW SHOULD BE PLACED PARALLEL TO THE SLOPE OR ALONG THE TOE OF SLOPE OR POINT OF BAR. IT SHOULD BE PLACED AT THE TOE OF SLOPE OR POINT OF BAR. THE WATER SHOULD DRAIN OVER THE FILL WITH A LOW POINT FROM WHICH IT CAN BE REMOVED. THE FILL SHOULD BE BAILED STRAW SHOULD BE PLACED AT THE TOE OF SLOPE OR POINT OF BAR. BAILED STRAW SHALL BE STAKED SECURELY TO THE GROUND.
(S42-G)	CONSTRUCTION SECTION 163		USED FOR INLETS RECEIVING RUNOFF WITH A HIGHER VOLUME OR VELOCITY. A GUYE FOR USE WILL BE FOR AN INLET RECEIVING A 0.5-1.0 CFS.
(S42-B)	CONSTRUCTION SECTION 163		USED FOR INLET PROTECTION WHERE HEAVY FLOWS ARE EXPECTED AND WHERE PROTECTIVE CAPACITY IS NECESSARY TO PREVENT EXCESSIVE POORING AROUND THE STRUCTURE. CAN BE USED AT INLET RECEIVING A 0.5-1.0 CFS.
(S42-P)	CONSTRUCTION SECTION 163		1. A SEDIMENT BARRIER CONSISTING OF A PREFABRICATED FRAME WITH FILTER FABRIC USED AROUND A GUYE FOR USE AS A CATCH BASIN. 2. A SEDIMENT BARRIER CONSISTING OF A PREFABRICATED FRAME WITH FILTER FABRIC USED AROUND A GUYE FOR USE AS A CATCH BASIN. THIS ITEM IS USED TO PREVENT SILT FROM ENTERING THE PIPE SYSTEM. NOT APPLICABLE TO INLETS RECEIVING CONCENTRATED FLOW 0.5-1.0 CFS.

NOTE:
1. DO NOT USE EROSION CONTROL ITEMS IN A FLOWING STREAM OR IN A TIDAL AREA BELOW HIGH TIDE.
2. FOR ADDITIONAL INFORMATION ON THE DESIGN AND APPLICATION OF EROSION CONTROL MEASURES SEE THE GEORGIA MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.

DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA
EROSION CONTROL LEGEND AND UNIFORM CODE SHEET
SHEET 5 OF 6
NO SCALE
NUMBER EC-L5
JANUARY 2007
52-5

CODE	PRACTICE STD. / SPC. / SECTION	DETAIL	DESCRIPTION
(S1)	CONSTRUCTION SECTION 1128 & 2332		A PIPE OR BOX CULVERT OUTLET HEADWALL WITH AN APRON AND DISTRIBUTION BENCH IS USED TO PREVENT EROSION AND TO DISBURSE WATER. IT IS USED ON THE OUTLET OF ALL BOX CULVERTS AND ON SP. AND LOGGED RIVERS. MAY BE USED BY INLET FOR FLOWING STREAMS OR ON SMALL PIPES WHEN OUTLET VELOCITY IS 12 FPS AND GREATER.
(S1-R)	CONSTRUCTION SECTION 603		THIS ITEM IS ADDED TO "S1" WHEN ADDITIONAL PROTECTION IS NEEDED. TYPE "RIP RAP" PLACED ON FILTER FABRIC SHOULD BE USED AT A 2' MINIMUM. MAY BE USED ON INLETS FOR FLOWING STREAMS. REFER TO CHARTS IN MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA FOR QUANTITY DETERMINATION.
(S4)	CONSTRUCTION SECTION 603		PROVIDING A ROUGH SOIL SURFACE WITH HORIZONTAL DEPRESSIONS, BY OPERATING A CLEATED COOPER ON THE SLOPE IN A VERTICAL DIRECTION, BEING SEPARATED SLOPES IN THE GRADING PROCESS TO CONSTRUCT BENCHES WILL INCREASE MOUND VELOCITY AND INCREASE THE CAPACITY OF WATER. IN MOST CASES THIS ITEM IS NOT REQUIRED TO BE SHOWN ON THE PLANS, BUT SHOULD BE COMPLETED BY THE CONTRACTOR UNDER ALL PROJECTS. IF SEPARATED SLOPES ARE USED ON THE PROJECT, THIS ITEM SHALL BE SHOWN WHERE SEPARATED SLOPES ARE TO BE USED.

NOTE:
1. DO NOT USE EROSION CONTROL ITEMS IN A FLOWING STREAM OR IN A TIDAL AREA BELOW HIGH TIDE.
2. FOR ADDITIONAL INFORMATION ON THE DESIGN AND APPLICATION OF EROSION CONTROL MEASURES SEE THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION - MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.


DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA
EROSION CONTROL LEGEND AND UNIFORM CODE SHEET
SHEET 6 OF 6
NO SCALE
NUMBER EC-L6
NOV. 2007
52-6

AEC
50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecatl.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

GEORGIA REGISTERED PROFESSIONAL LANDSCAPE ARCHITECT
GSLA #027118
GSLA #0980
EXP. 3-11-2012

EROSION CONTROL DETAILS



EXISTING CONDITIONS EROSION CONTROL NARRATIVE:

- DESCRIPTION OF THE NATURE OF CONSTRUCTION ACTIVITY: GRADING, UTILITY CONSTRUCTION, BUILDING AND DETENTION POND.
- THE SITE IS CURRENTLY UNDEVELOPED AND PAD GRADED. THERE ARE SEVERAL BERMS AND TEMPORARY DOWNDRAINS THROUGHOUT THE SITE.
- CRITICAL AREAS: THE SITE IS NOT LOCATED WITHIN 200 FEET OF STATE WATERS.

PHASE 1 EROSION CONTROL NARRATIVE:

- CONTRACTOR SHALL CONFIRM THREE WEEKS PRIOR TO BEGINNING CONSTRUCTION THAT THE N.O.I. HAS BEEN FILED AND ASSOCIATED FEES PAID. THE NOI AND FEES MUST BE SUBMITTED TO E.P.D. AND/OR THE LOCAL ISSUING AUTHORITY AT LATEST 14 DAYS PRIOR TO BEGINNING CONSTRUCTION.
- INSTALL ALL SILT FENCE (S41) AND CONSTRUCTION EXIT(S) (C6) SHOWN ON THE PHASE 1 PLAN.
- LAYOUT CONSTRUCTION ROADS, STAGING AREA PADS, HAZARDOUS WASTE CONTAINMENT AREAS AND TOPSOIL STOCKPILE AREAS.
- INSTALL THE TEMPORARY SEDIMENT BASIN(S) (S43) PER THE PLAN.
- SET CLEANOUT ELEVATION MARKER ON RISER AT PROPER ELEVATION.
- INSTALL OUTLET PROTECTION (S4) AT THE TEMPORARY SEDIMENT BASIN OUTLET(S).
- CLEAR THE REMAINING SITE AND INSTALL DIVERSION DIKE(S) AND DOWNDRAIN(S).
- REMOVE ACCUMULATED SEDIMENT FROM TEMPORARY SEDIMENT BASIN(S) WHEN SEDIMENT REACHES THE DEPTH SHOWN ON THE MARKER(S).
- INSTALL AND MAINTAIN ALL BMP'S SHOWN ON THE PHASE 1 PLAN IN ACCORDANCE WITH THE MANUAL FOR SEDIMENT AND EROSION CONTROL IN GEORGIA (LATEST EDITION).
- CALL ENGINEER AT 770-641-1942 FOR INSPECTION WITHIN SEVEN (7) DAYS AFTER THE INITIAL CONSTRUCTION ACTIVITIES COMMENCE.
- SETUP A MONITORING PROGRAM IN ACCORDANCE WITH THE PLANS AND PERMIT.

PHASE 2 EROSION CONTROL NARRATIVE:


- PRACTICE DUST CONTROL (D6) AND APPLY MULCH (D61) AND TEMPORARY SEEDING (D62) AS REQUIRED.
- CONTINUE MAINTENANCE OF BMP'S INSTALLED IN PHASE 1.
- MANIPULATE THE GRADES AS SHOWN AND INSTALL ALL STORM DRAINAGE STRUCTURES AS SHOWN.
- INSTALL ALL TEMPORARY SEDIMENT TRAPS (S42) AS SHOWN.
- INSTALL DETENTION POND(S) WITH RETROFIT (R1).
- INSTALL STORM OUTLET PROTECTION AT ALL HEADWALLS PER PLANS.
- SET CLEANOUT ELEVATION MARKER ON OUTLET CONTROL STRUCTURE AT PROPER ELEVATION.
- REMOVE ACCUMULATED SEDIMENT FROM DETENTION BASIN WHEN SEDIMENT REACHES THE DEPTH SHOWN ON THE MARKER.
- INSTALL AND MAINTAIN ALL BMP'S SHOWN ON THE PHASE II PLAN IN ACCORDANCE WITH THE MANUAL FOR SEDIMENT AND EROSION CONTROL IN GEORGIA (LATEST EDITION).
- CONTINUE MONITORING PROGRAM IN ACCORDANCE WITH THE PLANS AND PERMIT.

PHASE 3 EROSION CONTROL NARRATIVE:

- CONTINUE MAINTENANCE OF BMP'S THAT ARE CURRENTLY INSTALLED ON SITE.
- CONTINUE MONITORING PROGRAM IN ACCORDANCE WITH THE PLANS AND PERMIT.
- CONSTRUCT BUILDINGS AND PARKING.
- PLANT TREES AND SHRUBS, SPREAD TOPSOIL AND GRASS ALL DISTURBED AREAS UPON COMPLETION OF FINE GRADING AND CURB BACKFILLING.
- REMOVE ALL ACCUMULATED SILT FROM DETENTION POND AND TEMPORARY SEDIMENT TRAPS. SEE FINAL GRADING PLAN FOR DETENTION POND ELEVATIONS.
- EXCAVATE SEDIMENT FOREBAYS AND MICROPOOL, INSTALL RIP RAP AT POND INLETS.
- PLANT PERMANENT VEGETATION.
- ACHIEVE FINAL STABILIZATION OF ALL AREAS.
- REMOVE ALL SEDIMENT STORAGE DEVICES INCLUDING RETROFIT AND SILT FENCES.
- FILE N.O.I. WITH GEORGIA EPD.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED.
NOTE: STONE CHECK DAMS SHOULD NOT BE USED ON LIVE STREAMS.
DRAINAGE AREA:
FOR STONE CHECK DAMS, THE DRAINAGE AREA SHALL NOT EXCEED TWO ACRES.
HEIGHT:
THE CENTER OF THE CHECK DAM SHOULD BE AT LEAST 9 INCHES LOWER THAN OUTER EDGES. DAM HEIGHT MUST BE 2 FEET MAXIMUM MEASURED TO CENTER CHECK DAM.
SIDE SLOPES:
SIDE SLOPES SHALL BE 2:1 OR FLATTER.
SPACING:
TWO OR MORE CHECK DAMS IN SERIES SHALL BE USED FOR DRAINAGE AREAS GREATER THAN ONE ACRE. MAXIMUM SPACING BETWEEN DAMS SHOULD BE SUCH THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME ELEVATION AS THE TOP OF THE DOWN STREAM DAM.

GEOTEXTILES:
A GEOTEXTILE SHOULD BE USED AS A SEPARATOR BETWEEN THE GRADED STONE AND THE SOIL BASE AND ABUTMENTS. THE GEOTEXTILE WILL PREVENT THE MIGRATION OF SOIL PARTICLES FROM THE SUB GRADE INTO THE GRADED STONE. THE GEOTEXTILES SHALL BE SELECTED / SPECIFIED IN ACCORDANCE WITH AASHTO M288-96 SECTION 7.3 SEPARATION REQUIREMENTS, TABLE 3. GEOTEXTILES SHALL BE "SET" INTO THE SUBGRADE SOILS. THE GEOTEXTILE SHALL BE PLACED IMMEDIATELY ADJACENT TO THE SUBGRADE WITHOUT ANY VOIDS AND EXTEND FIVE FEET BEYOND THE DOWN STREAM TOE OF THE DAM TO PREVENT SOULR.
CONSTRUCTION SPECIFICATIONS:
THE FOLLOWING TYPES OF CHECK DAMS ARE USED FOR THIS STANDARD.
STONE CHECK DAMS: Cd-S
STONE CHECK DAMS SHOULD BE CONSTRUCTED OF GRADED SIZE 2-10 INCH STONE. MECHANICAL OR HAND PLACEMENT SHALL BE REQUIRED TO ENSURE COMPLETE COVERAGE OF ENTIRE WIDTH OF DITCH OR SWALE AND THAT CENTER OF DAM IS LOWER THAN EDGES.
MAINTENANCE:
PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED. SEDIMENT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF ONE-HALF THE ORIGINAL DAM HEIGHT OR BEFORE. IF THE AREA IS TO BE MOWED, CHECK DAMS SHALL BE REMOVED ONCE FINAL STABILIZATION HAS OCCURRED. OTHERWISE CHECK DAMS MAY REMAIN IN PLACE PERMANENTLY. AFTER REMOVAL, THE AREA BENEATH THE DAM SHALL BE SEEDED AND MULCHED IMMEDIATELY.



(Cd-S) STONE CHECK DAMS
NOT TO SCALE

DATE	REVISIONS	DATE	REVISIONS

ROSWELL
GEORGIA
SINCE 1854

WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

STATE	SHEET NO.	TOTAL SHEETS
GA	50	

CONSTRUCTION SPECIFICATIONS

MATERIALS
TOPSOIL SHOULD BE FRIABLE AND LOAMY, FREE OF DEBRIS, OBJECTIONABLE WEEDS AND STONES, AND CONTAIN NO TOXIC SUBSTANCE THAT MAY BE HARMFUL TO PLANT GROWTH. A PH RANGE OF 5.0-7.5 IS ACCEPTABLE. SOLUBLE SALTS SHOULD NOT EXCEED 500 PPM.

TESTING
FIELD EXPLORATION SHOULD BE MADE TO DETERMINE WHETHER THE QUANTITY AND QUALITY OF SURFACE SOIL JUSTIFIES STRIPPING.

STRIPPING
STRIPPING SHOULD BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. A 4 TO 6 INCH STRIPPING DEPTH IS COMMON, BUT MAY VARY DEPENDING ON THE PARTICULAR SOIL.

TOPSOIL PH
IF PH VALUE IS LESS THAN 6.0, LIME SHALL BE APPLIED AND INCORPORATED WITH THE TOPSOIL TO ADJUST THE PH TO 6.5 OR HIGHER. TOPSOILS CONTAINING SOLUBLE SALTS GREATER THAN 500 PARTS PER MILLION SHALL NOT BE USED.

STOCKPILES
THE LOCATION OF TOPSOIL STOCKPILES SHOULD NOT OBSTRUCT NATURAL DRAINAGE OR CAUSE OFF-SITE ENVIRONMENTAL DAMAGE.

STABILIZATION
STOCKPILES SHALL BE CONTAINED BY SEDIMENT BARRIERS TO PREVENT SEDIMENTATION ON ADJACENT AREAS. STOCKPILES SHALL BE STABILIZED IN ACCORDANCE WITH SPECIFICATIONS Ds1 AND Ds2 - DISTURBED AREA STABILIZATION (WITH MULCHING) AND (WITH TEMPORARY GRASSING), RESPECTIVELY, OR Pm - POLYACRYLAMIDE OR Td - TACKIFIERS AND BINDERS.

SITE PREPARATION (WHERE TOPSOIL IS TO BE ADDED)
TOPSOILING: WHEN TOPSOILING, MAINTAIN NEEDED EROSION CONTROL PRACTICES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, BERMS, DIKES, LEVEL SPREADERS, WATERWAYS, SEDIMENT BASINS, ETC.
GRADING: GRADES ON THE AREAS TO BE TOPSOILED WHICH HAVE BEEN PREVIOUSLY ESTABLISHED SHALL BE MAINTAINED.
LIMING: SOIL TESTS SHOULD BE USED TO DETERMINE THE PH OF THE SOIL. WHERE THE PH OF THE SUBSOIL IS 5.0 OR LESS OR COMPOSED OF HEAVY CLAYS, AGRICULTURAL LIMESTONE SHALL BE SPREAD AT THE RATE OF 100 POUNDS PER 1,000 SQUARE FEET. LIME SHALL BE DISTRIBUTED UNIFORMLY OVER DESIGNATED AREAS AND WORKED INTO THE SOIL IN CONJUNCTION WITH TILLAGE OPERATIONS AS DESCRIBED IN THE FOLLOWING PROCEDURE.
BONDING: USE ONE OF THE FOLLOWING METHODS TO INSURE BONDING OF TOPSOIL AND SUBSOIL:
1. TILLING AFTER THE AREAS TO BE TOPSOILED HAVE BEEN BROUGHT TO GRADE AND IMMEDIATELY PRIOR TO DUMPING AND SPREADING THE TOPSOIL, THE SUBGRADE SHALL BE LOOSENED BY DISCING OR SCARIIFYING TO A DEPTH OF AT LEAST 3 INCHES TO PERMIT BONDING OF THE TOPSOIL TO THE SUBSOIL.
2. TRACKING PASSING A BULLDOZER OVER THE ENTIRE SURFACE AREA OF THE SLOPE TO LEAVE HORIZONTAL DEPRESSIONS.

APPLYING TOPSOIL
1. TOPSOIL SHOULD BE HANDLED ONLY WHEN IT IS DRY ENOUGH TO WORK WITHOUT DAMAGING SOIL STRUCTURE.
2. A UNIFORM APPLICATION OF 5 INCHES (UNSETTLED) IS RECOMMENDED, BUT MAY BE ADJUSTED AT THE DISCRETION OF THE ENGINEER OR LANDSCAPE ARCHITECT.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
LOCATION: THE FILTER RING SHALL SURROUND ALL SIDES OF THE STRUCTURE RECEIVING RUNOFF FROM DISTURBED AREAS. IT SHOULD BE PLACED A MINIMUM OF FOUR FEET FROM THE STRUCTURE. THE RING IS NOT INTENDED TO SUBSTANTIALLY IMPOUND WATER, CAUSING FLOODING OR DAMAGE TO ADJACENT AREAS. THE FILTER RING MAY ALSO BE PLACED BELOW STORM DRAINS DISCHARGING INTO DETENTION PONDS, CREATING A CENTRALIZED AREA, OR "FOREBAY", FOR SEDIMENT ACCUMULATION. THIS PROVIDES FOR EASIER, MORE LOCALIZED CLEANOUT OF THE POND, IF UTILIZED ABOVE A RETROFIT STRUCTURE, IT SHOULD BE A MINIMUM OF 8 TO 10 FEET FROM THE RETROFIT.
STONE SIZE:
• WHEN UTILIZED AT INLETS WITH DIAMETERS LESS THAN 12 INCHES, THE FILTER RING SHALL BE CONSTRUCTED OF STONE NO SMALLER THAN 3-5 INCHES (15 - 30 LBS.).
• WHEN UTILIZED AT PIPES WITH DIAMETERS GREATER THAN 12 INCHES, THE FILTER RING SHALL BE CONSTRUCTED OF STONE NO SMALLER THAN 10-15 INCHES (50 - 100 LBS.).
• THE LARGER STONE ON THE UPSTREAM SIDE FOR ADDED SEDIMENT FILTERING CAPABILITIES. HOWEVER, THE SMALLER FILTER STONE IS MORE PRONE TO CLOGGING, REQUIRING HIGHER MAINTENANCE.
HEIGHT: THE FILTER RING SHALL BE CONSTRUCTED AT A HEIGHT NO LESS THAN TWO FEET FROM GRADE.
CONSTRUCTION SPECIFICATIONS
1. MECHANICAL OR HAND PLACEMENT OF STONE SHALL BE REQUIRED TO UNIFORMLY SURROUND THE STRUCTURE TO BE SUPPLEMENTED. REFER TO APPENDIX C FOR ROCK RIPRAP SPECIFICATIONS.
2. THE FILTER RING MAY BE CONSTRUCTED ON NATURAL GROUND SURFACE, ON AN EXCAVATED SURFACE, OR ON MACHINE-COMPACTED FILL.
3. A COMMON FAILURE OF FILTER RINGS IS CAUSED BY THEIR PLACEMENT TOO CLOSE OR TOO HIGH ABOVE THE STRUCTURE. WHEN UTILIZED BELOW A STORM DRAIN OUTLET, IT SHALL BE PLACED SUCH THAT IT DOES NOT CREATE A CONDITION CAUSING WATER TO BACK-UP INTO THE STORM DRAIN AND INHIBIT THE FUNCTION OF THE STORM DRAIN SYSTEM.




MAINTENANCE
THE FILTER RING MUST BE KEPT CLEAR OF TRASH AND DEBRIS. THIS WILL REQUIRE CONTINUOUS MONITORING AND MAINTENANCE, WHICH INCLUDES SEDIMENT REMOVAL WHEN ONE-HALF FULL. STRUCTURES ARE TEMPORARY AND SHOULD BE REMOVED WHEN THE LAND-DISTURBING PROJECT HAS BEEN STABILIZED.

TOPSOILING

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.


HAYBALE CHECK DAMS

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.



- NOTES:**
- EMBED BALES 4" INTO THE SOIL AND "KEY" BALES INTO THE CHANNEL BANKS.
 - POINT 'A' MUST BE HIGHER THAN POINT 'B'. (SPILLWAY HEIGHT)
 - PLACE BALES PERPENDICULAR TO THE FLOW WITH ENDS TIGHTLY ABUTTING.
 - SPILLWAY HEIGHT SHALL NOT EXCEED 24".
 - INSPECT AFTER EACH SIGNIFICANT STORM, MAINTAIN AND REPAIR PROMPTLY.
 - DO NOT TOE IN (EMBED) HAYBALES IN STREAM BUFFER AREAS.

DUST CONTROL ON DISTURBED AREAS



DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED:
STANDARD: POSTS SHALL BE USED IN CONJUNCTION WITH OTHER SEDIMENT CONTROL MEASURES. EXCEPT WHERE OTHER PRACTICES DEFINED IN THIS MANUAL ARE NOT APPROPRIATE (SUCH AS INLETS TO CONCRETE FLUMES), THEY CAN BE INSTALLED AT OR AROUND DEVICES SUCH AS INLET SEDIMENT TRAPS, TEMPORARY DOWNDRAIN INLETS, AND DETENTION POND RETROFITS TO PROVIDE ADDITIONAL SEDIMENT FILTERING CAPACITY.


DATE	REVISIONS	DATE	REVISIONS

DESIGN CRITERIA:
FORMAL DESIGN IS NOT REQUIRED. THE FOLLOWING STANDARDS SHALL BE USED.
AGGREGATE SIZE:
STONE WILL BE IN ACCORDANCE WITH NATIONAL STONE ASSOCIATION R-2 (1.5 TO 3.5 INCH STONE).
PAD THICKNESS:
THE GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES.
PAD WIDTH:
AT A MINIMUM, THE WIDTH SHOULD EQUAL FULL WIDTH OF ALL POINTS OF VEHICULAR EGRESS, BUT NOT LESS THAN 20 FEET WIDE.
WASHING:
IF THE ACTION OF THE VEHICLE TRAVELING OVER THE GRAVEL PAD DOES NOT SUFFICIENTLY REMOVE THE MUD, THE TIRES SHOULD BE WASHED PRIOR TO ENTRANCE OVER PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE AND PROMISSED THAT INTERCEPT THE SEDIMENT-LADEN RUNOFF AND DIRECT IT INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

CONSTRUCTION SPECIFICATIONS:
IT IS RECOMMENDED THAT THE ENTRANCE AREA BE EXCAVATED TO A DEPTH OF 3 INCHES AND BE CLEARED OF ALL VEGETATION AND ROOTS.
DIVERSION RIDGE:
ON SITES WHERE THE GRADE TOWARD THE PAVED AREA IS GREATER THAN 2%, A DIVERSION RIDGE 6 TO 8 INCHES HIGH WITH 3:1 SIDE SLOPES SHALL BE CONSTRUCTED ACROSS THE FOUNDATION APPROXIMATELY 15 FEET ABOVE THE ROAD.

GEOTEXTILE:
THE GEOTEXTILE UNDER LNER MUST BE PLACED THE FULL LENGTH AND WIDTH OF THE ENTRANCE. GEOTEXTILE SELECTION SHALL BE BASED ON AASHTO M288-96 SPECIFICATIONS:
1) FOR SUB-GRADES WITH A CBR GREATER THAN OR EQUAL TO 3 OR SHEAR STRENGTH GREATER THAN 90 KPA, GEOTEXTILE MUST MEET REQUIREMENTS OF SECTION AASHTO M288-96 SECTION 7.3, STABILIZATION REQUIREMENTS.
2) FOR SUB-GRADES WITH A CBR GREATER THAN OR EQUAL TO 3 OR SHEAR STRENGTH BETWEEN 30 AND 90 KPA, GEOTEXTILE MUST MEET REQUIREMENTS OF SECTION AASHTO M288-96 SECTION 7.4, STABILIZATION REQUIREMENTS.

MAINTENANCE:
THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1.5 - 3.5 INCH STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN OUT OF ANY STRUCTURES TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES OR SITE ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.



CONSTRUCTION EXIT

POSTS AND WOVEN WIRE SUPPORT:

TYPE "A" FENCE:
POSTS SHALL BE A MINIMUM OF 4 FEET LONG AND EITHER WOOD OR STEEL MAY BE USED. SOFT WOOD POSTS SHALL BE AT LEAST 3 INCHES IN DIAMETER OR NOMINAL 2"x4" AND STRAIGHT ENOUGH TO PROVIDE A FENCE WITHOUT NOTICEABLE MISALIGNMENT. IF HARDWOOD POSTS ARE USED THE SIZE MAY BE REDUCED TO 1 1/2" x 1 1/2" WITH A MINUS TOLERANCE. PROVIDE A MINIMUM OF 2.25 SQUARE INCHES. STEEL POSTS SHALL BE "U", "T", OR "C" SHAPED WITH A MINIMUM WEIGHT OF 1.3 POUNDS PER FOOT, AND HAVE PROJECTIONS FOR FASTENING THE FENCE TO THE POSTS. MAXIMUM POST SPACING SHALL BE 6 FEET.
TYPE "B" FENCE:
POSTS SHALL BE A MINIMUM OF 3 FEET LONG. SOFT WOOD POSTS SHALL BE AT LEAST 2 INCHES IN DIAMETER OR NOMINAL 2"x2". IF HARDWOOD POSTS ARE USED THE SIZE MAY BE REDUCED TO 1"x1" WITH A MINUS TOLERANCE OF 1" PROVIDING THE CROSS SECTIONAL AREA IS A MINIMUM OF ONE SQUARE INCH. STEEL POSTS SHALL BE "U", "T", OR "C" SHAPED WITH A MINIMUM WEIGHT OF 0.75 POUNDS PER FOOT MAY BE USED. MAXIMUM SPACING SHALL BE 6 FEET.
TYPE "C" FENCE:
POSTS SHALL BE STEEL AND HAVE A MINIMUM LENGTH OF 5 FEET. POSTS SHALL BE "U", "T", OR "C" SHAPED AND HAVE A MINIMUM WEIGHT OF 1.3 POUNDS PER FOOT. THE POSTS SHALL HAVE PROJECTIONS FOR FASTENING THE WOVEN WIRE AND FILTER FABRIC. MAXIMUM POSTS SPACING SHALL BE 4 FEET. A WOVEN WIRE SUPPORT FENCE SHALL BE USED WITH TYPE "C" FENCE. THE WIRE FENCE FABRIC SHALL BE AT LEAST 36 INCHES HIGH AND SHALL HAVE AT LEAST 6 HORIZONTAL WIRES. VERTICAL WIRES SHALL HAVE A MAXIMUM SPACING OF 12 INCHES. THE TOP AND BOTTOM WIRES SHALL BE AT LEAST 10 GAUGE AND ALL OTHER WIRES SHALL BE AT LEAST 12 GAUGE.

FASTENERS FOR WOODEN POSTS:
WIRE STAPLES:
STAPLES SHALL BE 17 GAUGE MINIMUM AND SHALL HAVE A CROWN 1/4" WIDE AND LEGS AT LEAST 1/2" LONG. STAPLES SHALL BE EVENLY SPACED WITH AT LEAST 5 PER POST USING DOUBLE STAPLES AT THE TOP POSITION.
NAILS:
NAILS SHALL BE 14 GAUGE MINIMUM, 1 INCH LONG WITH BUTTON HEADS. NAILS SHALL BE EVENLY SPACED WITH AT LEAST 5 PER POST FOR TYPE "A" FENCE AND 4 PER POST FOR TYPE "B" FENCE.


INSTALLATION:
1. INSTALL WHERE SHEET FLOW CONDITIONS EXIST.
2. WHERE NO SEDIMENT TRAP/STORMWATER DISPOSAL SYSTEM IS PRESENT, MAXIMUM SLOPE SHALL NOT EXCEED THOSE IN THE TABLE.
3. APPROVED SILT FENCE FABRICS ARE LISTED IN THE GEORGIA DEPARTMENT OF TRANSPORTATION QUALIFIED PRODUCTS LIST #36 (OPL-36). VERIFY FABRIC BY INSPECTION OF FABRIC NAME PRINTED EVERY 100 FEET OF SILT FENCE.
4. INSTALL ACCORDING TO APPROVED PLAN, AS SHOWN.
5. INSTALL ALONG CONTOURS WITH ENDS POINTING UPHILL.
6. DO NOT PLACE IN WATERWAYS OR AREAS OF CONCENTRATED FLOW.
7. INSTALL WHERE SHEET FLOW CONDITIONS EXIST.
8. DRAINAGE AREA NOT TO EXCEED 1/4 ACRE PER 100 FT. OF SILT FENCE.
9. VERIFY FABRIC BY INSPECTION OF FABRIC NAME PRINTED EVERY 100 FT. OF SILT FENCE.

10. START POST INSTALLATION AT THE CENTER OF THE LOWEST POINT WITH REMAINING POSTS SPACED ACCORDING TO FIGURE.
11. PROVIDE A RIPRAP SPLASH PAD OR OTHER OUTLET PROTECTION DEVICE FOR ANY POINT WHERE FLOW MAY TOP THE SEDIMENT FENCE. ENSURE THAT THE MAXIMUM HEIGHT OF THE FENCE AT A PROTECTED, REINFORCED OUTLET DOES NOT EXCEED 1 FT. AND THAT SUPPORT POST SPACING DOES NOT EXCEED 4 FT.
12. USE MINIMUM 16" OVERLAP AT FABRIC ENDS.
13. USE A DOUBLE ROW OF TYPE "C" SILT FENCE ALONG STREAM BUFFERS AND OTHER SENSITIVE AREAS.
14. A TRENCH 6 INCHES IN DEPTH FOR TYPES "A" AND "C", OR 4 INCHES IN DEPTH FOR TYPE "B", SHALL BE EXCAVATED WITH EQUIPMENT SUCH AS A TRENCHING MACHINE OR MOTOR GRADER; OR, IF EQUIPMENT CANNOT BE OPERATED ON THE SITE, BY HAND.

15. POST INSTALLATION SHALL START AT THE CENTER OF THE LOW POINT (IF APPLICABLE) WITH THE REMAINING POSTS SPACED A MAXIMUM OF 6 FEET APART FOR TYPE "A" AND "B" AND 4 FEET APART FOR TYPE "C". POSTS SHALL BE INSTALLED WITH AT LEAST 18 INCHES IN THE GROUND, WHERE AN 18 INCH DEPTH IS IMPOSSIBLE TO ACHIEVE, THE POSTS SHALL BE ADEQUATELY SECURED TO PREVENT OVERTURNING IF THE FENCE DUE TO SEDIMENT LOADING.
16. FILTER FABRIC SHALL BE ATTACHED TO THE POST BY WIRE, CORD, POCKETS, STAPLES, NAILS, OR OTHER ACCEPTABLE MEANS. THE FILTER FABRIC SHALL BE INSTALLED IN SUCH A MANNER THAT 6 INCHES (TYPE "B") OR 8 INCHES (TYPES "A" AND "C") OF FABRIC IS LEFT AT THE BOTTOM TO BE BURIED AND A MINIMUM OVERLAP OF 18 INCHES IS PROVIDED AT ALL SPICE JOINTS. THE FABRIC SHALL BE INSTALLED IN THE TRENCH SUCH THAT 4 TO 6 INCHES OF FABRIC IS AGAINST THE SIDE OF THE TRENCH WITH 2 TO 4 INCHES OF FABRIC ACROSS THE BOTTOM IN THE UPSTREAM DIRECTION.

MAINTENANCE:
1. INSPECT BARRIERS AT THE END OF EACH WORKING DAY, OR AFTER EACH RAIN, AND REPAIR OR CLEAN AS NECESSARY.
2. REMOVE SEDIMENT FROM BARRIER ONCE IT HAS ACCUMULATED TO ONE-HALF THE ORIGINAL HEIGHT OF THE BARRIER.
3. PROPERLY DISPOSE OF SEDIMENT AND STABILIZE IT WITH VEGETATION.
4. REPLACE FILTER FABRIC WHEN DETRIORATED.
5. DESIGN LIFE OF A SYNTHETIC SILT FENCE IS APPROXIMATELY 6 MONTHS.
6. MAINTAIN UNTIL THE PROJECT IS VEGETATED OR OTHERWISE STABILIZED.
7. REMOVE BARRIERS AND ACCUMULATED SEDIMENT AND STABILIZE THE EXPOSED AREA WHEN THE PROJECT IS STABILIZED.

EXTRA STRENGTH FILTER FABRIC NEEDED WITHOUT WIRE MESH SUPPORT
TYPE "A" WOOD OR STEEL POSTS MIN. 4' LONG
TYPE "B" WOOD OR STEEL POSTS MIN. 3' LONG
TYPE "C" STEEL POSTS MIN. 4' LONG



SILT FENCE ALTERNATIVE:
1. THE C-POP SEDIMENT BARRIER SYSTEM CAN BE A SUBSTITUTE FOR TRADITIONAL TYPE C STEEL POSTED, WIRE REINFORCED SILT FENCE.
2. INSTALL PER TRADITIONAL TYPE C SILT FENCE SPECIFICATIONS AND MANUFACTURERS SPECIFICATIONS.

DESIGN CRITERIA:
TYPE "A" - PROJECT LIFE SPAN GREATER THAN 6 MONTHS, AND/OR SLOPE GRADIENT IS STEEPER THAN 3:1
TYPE "B" - PROJECT LIFE SPAN IS LESS THAN 6 MONTHS, AND SLOPE IS LESS THAN OR EQUAL TO 3:1
TYPE "C" - FILL SLOPES EXCEED A VERTICAL HEIGHT OF 20 FEET AND THE SLOPE GRADIENT IS STEEPER THAN 3:1 OR RUNOFF FLOWS OR VELOCITIES ARE HIGH.
DOUBLE ROW OF TYPE C - ALONG STREAM BUFFERS AND OTHER SENSITIVE AREAS


FILTER FABRICS:
APPROVED SILT FENCE FABRICS ARE LISTED IN THE GEORGIA DEPARTMENT OF TRANSPORTATION QUALIFIED PRODUCTS LIST #36 (OPL-36).
THE FABRIC SHALL MEET THE FOLLOWING PHYSICAL OR DIMENSIONAL REQUIREMENTS.

FABRIC REQUIREMENTS			
TYPE FENCE:	A	B	C
TENSILE STRENGTH (LBS. MIN.) (1) (ASTM D-4632)	WRAP-120 FILL-100	WRAP-120 FILL-100	WRAP-120 FILL-180
ELONGATION (%MAX.) (ASTM D-4632)	40	40	40
AOS (APPARENT OPENING SIZE) (MAX. SIEVE SIZE) (ASTM D-4751)	NO. 30	NO. 30	NO. 30
FLOW RATE, GAL/MIN/FT2 (GDT-87)	25	25	70
ULTRAVIOLET STABILITY (2) (ASTM D-4632 AFTER 300 HOURS WEATHERING IN ACCORDANCE WITH ASTM D-4355)	80	80	80
BURSTING STRENGTH, (PSI MIN) (ASTM D-3785 DIAPHRAGM BURSTING STRENGTH TESTER)	175	175	175
MINIMUM FABRIC WIDTH (IN)	36	22	36

(1) MINIMUM ROLL AVERAGE OF FIVE SPECIMENS.
(2) PERCENT OF REQUIRED INITIAL MINIMUM TENSILE STRENGTH.

SLOPE LENGTH CRITERIA FOR SILT FENCE PLACEMENT

LAND SLOPE (PERCENT)	MAX. SLOPE LENGTH BEHIND FENCE (FEET)
< 2	100
2 TO 5	75
5 TO 10	50
10 TO 20	25
> 20"	15



SILT FENCE SEDIMENT BARRIER

A-EC
50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

GEORGIA REGISTERED PROFESSIONAL ENGINEER
NO. 00118
W. VANDEWATER

GSWCC #8960
EXP. 3-11-2012

EROSION CONTROL DETAILS



WILLEO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

MATERIALS:
 ALL BLANKET AND MATTING MATERIALS SHALL BE ON THE GEORGIA DEPARTMENT OF TRANSPORTATION QUALIFIED PRODUCTS LIST (OPL # 62 FOR BLANKETS, OPL # 49 FOR MATTING). ALL BLANKETS SHALL BE NON-TOXIC TO VEGETATION AND TO THE GERMINATION OF SEED AND SHALL NOT BE INJURIOUS TO THE UNPROTECTED SKIN OF HUMANS. AT A MINIMUM, THE PLASTIC NETTING SHALL BE INTERTWINED WITH THE MULCHING MATERIAL / FIBER TO MAXIMIZE STRENGTH AND PROVIDE FOR EASE OF HANDLING.

TEMPORARY BLANKETS: MACHINE PRODUCED TEMPORARY COMBINATION BLANKETS SHALL HAVE A CONSISTENT THICKNESS WITH THE ORGANIC MATERIAL EVENLY DISTRIBUTED OVER THE ENTIRE BLANKET AREA. ALL COMBINATION BLANKETS SHALL HAVE A MINIMUM WIDTH OF 48 INCHES. MACHINE PRODUCED COMBINATION BLANKETS INCLUDE THE FOLLOWING:

STRAW BLANKETS: COMBINATION BLANKETS THAT CONSIST OF WEED-FREE STRAW FROM AGRICULTURAL CROPS FORMED INTO A BLANKET. BLANKETS WITH A TOPSIDE OF PHOTO DEGRADABLE PLASTIC MESH WITH A MAXIMUM MESH SIZE OF 3/8 X 3/8 INCH AND SEWN TO THE STRAW WITH BIODEGRADABLE THREAD IS APPROPRIATE FOR SLOPES. THE BLANKET SHALL HAVE A MINIMUM THICKNESS OF 3/8 INCH AND MINIMUM DRY WEIGHT OF 0.5 POUNDS PER SQUARE YARD.

EXCELISOR BLANKETS: COMBINATION BLANKETS THAT CONSIST OF CURLED WOOD EXCELISOR (80% OF FIBERS ARE SIX INCHES OR LONGER) FORMED INTO A BLANKET. THE BLANKET SHALL HAVE CLEAR MARKINGS INDICATING THE TOP SIDE OF THE BLANKET AND BE SMOOTHER RESISTANT. BLANKETS SHALL HAVE PHOTO DEGRADABLE PLASTIC MESH HAVING A MAXIMUM MESH SIZE OF 1 1/2 X 3 INCHES. THE BLANKET SHALL HAVE A MINIMUM THICKNESS OF 1/2 OF AN INCH AND A MINIMUM DRY WEIGHT OF 0.8 POUNDS PER SQUARE YARD. SLOPES REQUIRE EXCELISOR MATTING WITH THE TOP SIDE OF THE BLANKET COVERED IN THE PLASTIC MESH, AND FOR WATERWAYS, BOTH SIDES OF THE BLANKET REQUIRE PLASTIC MESH.

COCONUT FIBER BLANKETS: COMBINATION BLANKETS THAT CONSIST OF 100% COCONUT FIBER FORMED INTO A BLANKET. THE MINIMUM THICKNESS OF THE BLANKET SHALL BE 3/8 OF AN INCH WITH A MINIMUM DRY WEIGHT OF 0.5 POUNDS PER SQUARE YARD. BLANKETS SHALL HAVE PHOTO DEGRADABLE PLASTIC MESH, WITH A MAXIMUM MESH SIZE OF 3/8 X 3/8 INCH AND SEWN TO THE FIBER WITH A BREAKDOWN RESISTANT SYNTHETIC YARN. PLASTIC MESH IS REQUIRED ON BOTH SIDES OF THE BLANKET IF USED IN WATERWAYS. A MAXIMUM OF TWO INCHES IS ALLOWABLE FOR THE STITCH PATTERN AND ROW SPACING.

WOOD FIBER BLANKETS: COMBINATION BLANKET THAT CONSIST OF REPROCESSED WOOD FIBERS THAT DO NOT POSSESS OR CONTAIN ANY GROWTH OR GERMINATION INHIBITING FACTORS. THE BLANKET SHALL HAVE A PHOTO DEGRADABLE PLASTIC MESH, WITH A MAXIMUM MESH SIZE OF 3/8 X 3/8 INCH, SECURELY BONDED TO THE TOP OF THE MAT. THE BLANKET SHALL HAVE A MINIMUM DRY WEIGHT OF 0.35 POUNDS PER SQUARE YARD. A MAXIMUM OF TWO INCHES IS ALLOWABLE FOR THE STITCH PATTERN AND ROW SPACING. THIS PRACTICE SHALL BE APPLIED ONLY TO SLOPES.

JUTE MESH: CAN BE APPLIED TO SLOPES. JUTE MESH WITH A 48 INCH WIDTH SHALL SHOW BETWEEN 76 AND 80 WARPINGS AND A ONE YARD LENGTH SHALL SHOW BETWEEN 39 TO 43 WEFTINGS. THE WOVEN MESH SHALL BE AT LEAST 45 INCHES WIDE. YARN SHALL HAVE A UNIT WEIGHT OF AT LEAST 0.9 POUNDS PER SQUARE YARD, BUT NOT MORE THAN 1.5 POUNDS PER SQUARE YARD.

PERMANENT MATTING: PERMANENT MATTING SHALL CONSIST OF A LOFTY WEB OF MECHANICALLY OR MELT BONDED POLYMER NETTINGS, MONOFILAMENTS OR FIBERS WHICH ARE ENTANGLED TO FORM A STRONG AND DIMENSIONALLY STABLE MATRIX. POLYMER WELDING, THERMAL OR POLYMER FUSION, OR THE PLACEMENT OF FIBERS BETWEEN TWO HIGH STRENGTH, BIAXIALLY ORIENTED NETS BOUND SECURELY TOGETHER BY PARALLEL STITCHING WITH POLYOLEFIN, NYLON OR POLYESTER THREADS ARE ALL APPROPRIATE BONDING METHODS. MATS SHALL MAINTAIN THEIR SHAPE BEFORE, DURING AND AFTER INSTALLATION, UNDER DRY OR WATER SATURATED CONDITIONS. MATS MUST BE STABILIZED AGAINST ULTRAVIOLET DEGRADATION AND SHALL BE INERT TO CHEMICALS NORMALLY ENCOUNTERED IN A NATURAL SOIL ENVIRONMENT. THE MAT SHALL CONFORM TO THE FOLLOWING PHYSICAL PROPERTIES.

PERMANENT MAT PHYSICAL PROPERTY REQUIREMENTS

PROPERTY	MINIMUM VALUE
THICKNESS	0.5 INCHES
WEIGHT	0.6 PSY
ROLL WIDTH	38 IN.
TENSILE STRENGTH:	
LENGTH (50% ELONGATION)	15 LBSIN
LENGTH (ULTIMATE)	20 LBSIN
WIDTH (50% ELONGATION)	5 LBSIN
WIDTH (ULTIMATE)*	10 LBSIN
ULTRAVIOLET STABILITY	80%

(1000 HOURS IN AN ATLAS ARC WEATHEROMETER, ASTM G 23, TYPE D, IN ACCORDANCE WITH ASTM D 822)

*ASTM D 1682 - 6" STRIP


SITE PREPARATION:
 AFTER THE SITE HAS BEEN SHAPED AND GRADED TO THE APPROVED DESIGN, PREPARE A FRIABLE SEED BED RELATIVELY FREE FROM CLODS AND ROCKS MORE THAN ONE INCH IN DIAMETER, AND ANY FOREIGN MATERIAL THAT WILL PREVENT CONTACT OF THE SOIL STABILIZATION MAT WITH THE SOIL SURFACE. SURFACE MUST BE SMOOTH TO ENSURE PROPER CONTACT OF BLANKETS OR MATTING TO THE SOIL SURFACE. IF NECESSARY, REDIRECT ANY RUNOFF FROM THE DITCH OR SLOPE DURING INSTALLATION.

STAPLES:
 THE FOLLOWING ARE CONSIDERED APPROPRIATE STAPLING AND STAKING MATERIALS.
TEMPORARY BLANKETS: THIS INCLUDES STRAW, EXCELISOR, COCONUT FIBER, AND WOOD FIBER BLANKETS. STAPLES SHALL BE USED TO ANCHOR TEMPORARY BLANKETS. U-SHAPED WIRE (11 GAUGE OR GREATER) STAPLES WITH LEGS AT LEAST 6 INCHES IN LENGTH AND A CROWN OF ONE INCH OR APPROPRIATE BIODEGRADABLE STALE CAN BE USED. STAPLES SHALL BE OF SUFFICIENT THICKNESS FOR SOIL PENETRATION WITHOUT UNDUCE DISTORTION.
PERMANENT MATTING: SOUND WOOD STAPLES, 1 X 3 INCHES STOCK SAWS IN A TRIANGULAR SHAPE, SHALL BE USED, DEPENDING ON THE COMPACTION OF THE SOIL. SELECT STAPLES WITH A LENGTH FROM 12 TO 18 INCHES. U-SHAPED STAPLES SHALL BE 11 GAUGE STEEL OR GREATER, WITH LEGS AT A MINIMUM OF 6 INCHES LENGTH WITH A 2 INCH CROWN.

PLANTING:
 LIME, FERTILIZER, AND SEED SHALL BE APPLIED IN ACCORDANCE WITH SEEDING OR OTHER TYPE OF PLANTING PLAN COMPLETED PRIOR TO INSTALLATION OF TEMPORARY COMBINATION BLANKETS OR JUTE MESH. FOR PERMANENT MATS, THE AREA MUST BE BROUGHT TO FINAL GRADE, PLOWED, LIMED, AND FERTILIZED. AFTER THE PERMANENT MAT HAS BEEN INSTALLED AND BACKFILLED THE ENTIRE AREA SHALL BE GRASSED. REFER TO SPECIFICATION D63


INSTALLATION:
 SEE FIGURE FOR TYPICAL INSTALLATION GUIDELINES. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR LAYING AND STAPLING.

MAINTENANCE:
 ALL EROSION CONTROL BLANKETS AND MATTING SHOULD BE INSPECTED PERIODICALLY FOLLOWING INSTALLATION, PARTICULARLY AFTER INSTANTLY TO CHECK FOR EROSION AND UNDERMINING. ANY DISLOCATION OR FAILURE SHOULD BE REPAIRED IMMEDIATELY. IF WASHOUTS OR BREAKAGE OCCURS, REINSTALL THE MATERIAL AFTER REPAIRING DAMAGE TO THE SLOPE OR DITCH. CONTINUE TO MONITOR THESE AREAS UNTIL THEY BECOME PERMANENTLY STABILIZED.




- SEQUENTIAL ROLL INSTALLATION STEPS:**
1. START AT DOWNSTREAM TERMINAL AND PROGRESS UPSTREAM.
 2. FIRST ROLL IS CENTERED LONGITUDINALLY IN MID CHANNEL AND PINNED WITH TEMPORARY STAKES TO MAINTAIN ALIGNMENT.
 3. SUBSEQUENT ROLLS FOLLOW IN STAGGERED SEQUENCE BEHIND FIRST ROLL. USE CENTER ROLL FOR ALIGNMENT TO CHANNEL CENTER.
 4. WORK OUTWARDS FROM CHANNEL CENTER TO EDGE.
 5. USE 3" OVERLAP AND STAKE AT 5' INTERVAL ALONG SEAMS.
 6. USE 3" OVERLAPS AND SHINGLE DOWNSTREAM TO CONNECT LINING AT ROLL ENDS.


DOWNSTREAM TERMINAL INSTALLATION:



STEP 1: CUT TERMINAL SLOT.




STEP 2: STAKE MAT INTO SLOT.




STEP 3: BACKFILL TERMINAL SLOT.

- STEP 4:
- A. ROLL MAT UP STREAM OVER REFILLED TERMINAL.
 - B. STAKE MAT DOWN TO ANCHOR TERMINAL.
 - C. PROGRESS UPSTREAM WITH ROLL.


TRANSVERSE CHECK SLOT INSTALLATION:



STEP 1: CUT CHECK SLOT. TEMPORARILY STAKE MAT UNDER MODERATE TENSION.




STEP 2: WORK UPSTREAM ACROSS. CHECK SLOT LAP BACK 15°.




STEP 3: TUCK MAT LAP INTO SLOT AND STAKE.

- STEP 4:
- A. ROLL MAT UP STREAM OVER REFILLED TERMINAL.
 - B. STAKE MAT DOWN TO ANCHOR TERMINAL.
 - C. PROGRESS UPSTREAM WITH ROLL.


UPSTREAM TERMINAL INSTALLATION:




STEP 1: CUT TERMINAL SLOT.




STEP 2: SNUG MAT INTO SLOT.



- STEP 3:
- A. STAKE MAT INTO SLOT.
 - B. USE 1"-3" PRESSURE-TREATED BOARD TO BRACE MAT AGAINST VERTICAL CUT.
 - C. BACKFILL AND COMPACT.



- STEP 4:
- A. REVERSE MAT ROLL DIRECTION TO OVERLAY CHECK SLOT.
 - B. STAKE MAT TO ANCHOR TERMINAL.



PICTORIAL VIEW OF TRANSVERSE SLOT

(Mb) EROSION CONTROL MATTING AND BLANKETS NOT TO SCALE

CONDITIONS:
FLOC LOGS
 THIS TEMPORARY PRACTICE IS NOT INTENDED FOR APPLICATION TO SURFACE WATER OF THE STATE. IT IS INTENDED FOR APPLICATION WITHIN CONSTRUCTION STORM WATER DITCHES AND STORM DRAINAGES WHICH FEED INTO PRE-CONSTRUCTED SEDIMENT PONDS OR BASINS.

DUST CONTROL
 THIS TEMPORARY PRACTICE IS INTENDED FOR DIRECT SOIL SURFACE APPLICATION TO SITES WHERE THE TIMELY ESTABLISHMENT OF VEGETATION MAY NOT BE FEASIBLE OR WHERE VEGETATIVE COVER IS ABSENT OR INADEQUATE.

FEDERAL STATE AND LOCAL LAW.
 ANIONIC PAM APPLICATION SHALL COMPLY WITH ALL FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS GOVERNING ANIONIC PAM. THE OPERATOR IS RESPONSIBLE FOR SECURING REQUIRED PERMITS. THIS STANDARD DOES NOT CONTAIN THE TEXT OF THE FEDERAL, STATE OR LOCAL LAWS GOVERNING ANIONIC PAM.

PLANNING CONSIDERATIONS
 ANIONIC PAM IS AVAILABLE IN EMULSIONS, POWDERS, AND GEL BARS OR LOGS. IT IS REQUIRED THAT OTHER BEST MANAGEMENT PRACTICES BE USED IN COMBINATION WITH ANIONIC PAM.

THE USE OF SEED AND MULCH FOR ADDITIONAL EROSION PROTECTION BEYOND THE LIFE OF THE ANIONIC PAM IS RECOMMENDED. REPEAT APPLICATION IF DISTURBANCE OCCURS TO TARGET AREA.

THE FOLLOWING ARE ADDITIONAL RECOMMENDATIONS RELATING TO DESIGN WHICH MAY ENHANCE THE USE OF OR AVOID PROBLEMS WITH THE PRACTICE.


1. USE SETBACKS WHEN APPLYING ANIONIC PAM NEAR NATURAL WATERBODIES.
2. CONSIDER THAT DECREASED PERFORMANCE CAN OCCUR DUE TO ULTRAVIOLET LIGHT AND TIME AFTER MIXING WHEN APPLYING ANIONIC PAM.
3. IN FLOW CONCENTRATION CHANNELS, THE EFFECTIVENESS OF ANIONIC PAM FOR STABILIZATION DECREASES.
4. MULCH TO PROTECT SEED IF SEED IS APPLIED WITH ANIONIC PAM.
5. NEVER ADD WATER TO PAM, ADD PAM SLOWLY TO WATER. IF WATER IS ADDED TO PAM, "GLOBS" CAN FORM WHICH CAN CLOG DISPENSERS. THIS SIGNIFIES INCOMPLETE DISSOLUTION OF THE PAM AND THEREFORE INCREASES THE RISK OF UNDER-APPLICATION.
6. NOT ALL POLYMERS ARE PAM.

(Pm) POLYACRYLAMIDE (PAM) NOT TO SCALE

OPERATION AND MAINTENANCE
 MAINTENANCE WILL CONSIST OF REAPPLYING ANIONIC PAM TO DISTURBED AREAS, INCLUDING HIGH TRAFFIC AREAS WHICH INTERFERE IN THE PERFORMANCE OF THIS PRACTICE.

CRITERIA:

1. APPLICATION RATES SHALL CONFORM TO MANUFACTURER'S GUIDELINES FOR APPLICATION.
2. ONLY THE ANIONIC FORM OF PAM SHALL BE USED. CATIONIC PAM IS TOXIC AND SHALL NOT BE USED.
3. PAM AND PAM MIXTURES SHALL BE ENVIRONMENTALLY BENIGN, HARMLESS TO FISH, WILDLIFE, AND PLANTS. PAM AND PAM MIXTURES SHALL BE NON-COMBUSTIBLE.
4. ANIONIC PAM, IN PURE FORM, SHALL HAVE LESS THAN OR EQUAL TO 0.05% ACRYLAMIDE MONOMER BY WEIGHT, AS ESTABLISHED BY THE FOOD AND DRUG ADMINISTRATION AND THE ENVIRONMENTAL PROTECTION AGENCY.
5. TO MAINTAIN LESS THAN OR EQUAL TO 0.05% OF ACRYLAMIDE MONOMER, THE MAXIMUM APPLICATION RATE OF PAM IN PURE FORM SHALL NOT EXCEED 200 POUNDS PER ACRE/YEAR. DO NOT OVER APPLY PAM. EXCESSIVE APPLICATION OF PAM CAN LOWER INFILTRATION RATE OR SUSPEND SOILS IN WATER, RATHER THAN PROMOTING SETTLING.
6. USERS OF ANIONIC PAM SHALL OBTAIN AND FOLLOW ALL MATERIAL SAFETY DATA SHEET REQUIREMENTS AND MANUFACTURER'S RECOMMENDATIONS.
7. ADDITIVES SUCH AS FERTILIZERS, SOLUBILITY PROMOTERS OR INHIBITORS, ETC. TO PAM SHALL BE NON-TOXIC.
8. THE MANUFACTURER OR SUPPLIER SHALL PROVIDE WRITTEN APPLICATION METHODS FOR PAM AND PAM MIXTURES. THE APPLICATION METHOD SHALL INSURE UNIFORM COVERAGE TO THE TARGET AND AVOID DRIFT TO NON-TARGET AREAS INCLUDING WATERS OF THE STATE. THE MANUFACTURER OF SUPPLIER SHALL ALSO PROVIDE WRITTEN INSTRUCTIONS TO INSURE PROPER SAFETY, STORAGE, AND MIXING OF THE PRODUCT.
9. GEL BARS OR LOGS OF ANIONIC PAM MIXTURES MAY BE USED IN DITCH SYSTEMS. THIS APPLICATION SHALL MEET THE SAME TESTING REQUIREMENTS AS ANIONIC PAM EMULSIONS AND POWDERS.
10. TO PREVENT EXCEEDING THE ACRYLAMIDE MONOMER LIMIT IN THE EVENT OF A SPILL, THE ANIONIC PAM IN PURE FORM SHALL NOT EXCEED 200 POUNDS PER BATCH AT 0.05% ACRYLAMIDE MONOMER (ADM) OR 400 POUNDS PER BATCH AT 0.025% ADM.



(Bf) BUFFER ZONE

SPECIFICATIONS

PURPOSE:
 TO PROVIDE A BUFFER ZONE TO:

1. REDUCE STORM RUNOFF VELOCITIES
2. ACT AS SCREEN FOR "VISUAL POLLUTION"
3. REDUCE CONSTRUCTION NOISE
4. IMPROVE AESTHETICS ON THE DISTURBED LAND
5. FILTERING AND INFILTRATING RUNOFF
6. COOLING RIVERS AND STREAMS
7. PROVIDE FOOD AND COVER FOR WILDLIFE
8. FLOOD PROTECTION
9. PROTECT CHANNEL BANKS FROM SCOUR AND EROSION

DESIGN PRINCIPALS

1. SHEET FLOW SHOULD BE ENCOURAGED AT THE EDGE OF THE VEGETATED STREAM BUFFER.
2. THE STRUCTURE OF THE BUFFER SHOULD CONSIST OF UNDERSTORY AND CANOPY SPECIES. SHRUBS OR UNDERSTORY TREES SHOULD ONLY BE USED ON THIS PROJECT.
3. THE WIDTH SHOULD BE PROPORTIONAL TO THE WATERSHED AREA AND SLOPE.
4. NATIVE AND NON-INVASIVE PLANT SPECIES SHOULD BE USED.
5. DENSITY MUST BE CONSIDERED TO DETERMINE IF THE EXISTING BUFFER MUST BE ENHANCED TO ACHIEVE THE NECESSARY GOALS.
6. VEGETATION MUST BE DENSE ENOUGH TO FILTER SEDIMENT AND PROVIDE DETRITAL NUTRIENTS FOR AQUATIC ORGANISM.
7. USE STREAM BANK STABILIZATION TECHNIQUES ON STEEP SLOPES (USING PERMANENT VEGETATION).
8. PLANTINGS FOR BUFFER RE-ESTABLISHMENT AND ENHANCEMENT CAN CONSIST OF BARE ROOT SEEDLINGS, CONTAINER-GROWN SEEDLINGS, CONTAINER-GROWN PLANTS, AND BALLED AND BURLAPPED PLANTS. (REFER TO TABLES IN D63 - DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION) ON SHEET ESC-50). STANDARD PERMANENT EROSION CONTROL GRASSES AND LEGUMES MAY BE USED IN DENUDATED AREAS FOR QUICK STABILIZATION. STREAMBANK STABILIZATION TECHNIQUES MAY BE REQUIRED IF STEEP SLOPES AND HYDROLOGIC PATTERNS DEEM IT NECESSARY (REFER TO SPECIFICATION Sb - STREAMBANK STABILIZATION (USING PERMANENT VEGETATION)).
9. SEE TABLES 6-1.1 AND 6-1.2 FOR SUGGESTED PLANT MATERIAL.

A-EC
 LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE

GEORGIA REGISTERED PROFESSIONAL LANDSCAPE ARCHITECT
 No. 027116
 GSWCC #6980
 EXP. 3-11-2012

EROSION CONTROL DETAILS

DATE	REVISIONS	DATE	REVISIONS

ROSWELL
 GEORGIA
 SINCE 1854

WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS

STORM DRAIN OUTLET PROTECTION


DESIGN CRITERIA:
STRUCTURALLY LINED APRONS AT THE OUTLETS OF PIPES AND PAVED CHANNEL SECTIONS SHALL BE DESIGNED ACCORDING TO THE FOLLOWING CRITERIA:
CAPACITY
PEAK STORMFLOW FROM THE 25-YEAR, 24 HOUR FREQUENCY STORM OR THE STORM SPECIFIED IN THE TITLE 12-7-1 OF THE OFFICIAL CODE OF GEORGIA ANNOTATED OR THE DESIGN DISCHARGE OF THE WATER CONVEYANCE STRUCTURE, WHICHEVER IS GREATER.
TAILWATER DEPTH
THE DEPTH OF THE TAILWATER IMMEDIATELY BELOW THE PIPE OUTLET MUST BE DETERMINED FOR THE DESIGN CAPACITY OF THE PIPE. MANNING'S EQUATION MAY BE USED TO DETERMINE TAILWATER DEPTH. IF THE TAILWATER DEPTH IS LESS THAN HALF THE DIAMETER OF THE OUTLET PIPE, IT SHALL BE CLASSIFIED AS A MINIMUM TAILWATER CONDITION. IF THE TAILWATER DEPTH IS GREATER THAN HALF THE PIPE DIAMETER, IT SHALL BE CLASSIFIED AS A MAXIMUM TAILWATER CONDITION. PIPES WHICH OUTLET ONTO FLAT AREAS WITH NO DEFINED CHANNEL MAY BE ASSUMED TO HAVE A MINIMUM TAILWATER CONDITION.

APRON WIDTH
IF THE PIPE DISCHARGES DIRECTLY INTO A WELL-DEFINED CHANNEL, THE APRON SHALL EXTEND ACROSS THE CHANNEL BOTTOM AND UP THE CHANNEL BANKS TO AN ELEVATION ONE FOOT ABOVE THE MAXIMUM TAILWATER DEPTH OR TO THE TOP OF THE BANK (WHICHEVER IS LESS). IF THE PIPE DISCHARGES ONTO A FLAT AREA WITH NO DEFINED CHANNEL, THE WIDTH OF THE APRON SHALL BE DETERMINED AS FOLLOWS:
A. THE UPSTREAM END OF THE APRON, ADJACENT TO THE PIPE, SHALL HAVE A WIDTH THREE TIMES THE DIAMETER OF THE OUTLET PIPE.
B. FOR THE MINIMUM TAILWATER CONDITION, THE DOWNSTREAM END OF THE APRON SHALL HAVE A WIDTH EQUAL TO THE PIPE DIAMETER PLUS THE LENGTH OF THE APRON. REFER TO FIGURE 6-24.1.
C. FOR A MAXIMUM TAILWATER CONDITION, THE DOWN STREAM END SHALL HAVE A WIDTH EQUAL TO THE PIPE DIAMETER PLUS 0.4 TIMES THE LENGTH OF THE APRON. REFER TO FIGURE 6-24.2.

BOTTOM GRADE
THE APRON SHALL BE CONSTRUCTED WITH NO SLOPE ALONG ITS LENGTH (0.0% GRADE). THE INVERT ELEVATION OF THE DOWNSTREAM END OF THE APRON SHALL BE EQUAL TO THE ELEVATION OF THE INVERT OF THE RECEIVING CHANNEL. THERE SHALL BE NO OVERFALL AT THE END OF THE APRON.

SIDE SLOPE
IF THE PIPE DISCHARGES INTO A WELL-DEFINED CHANNEL, THE SIDE SLOPES OF THE CHANNEL SHALL NOT BE STEEPER THAN 2:1.

ALIGNMENT
THE APRON SHALL BE LOCATED SO THAT THERE ARE NO BENDS IN THE HORIZONTAL ALIGNMENT.
GEOTEXTILE
GEOTEXTILES SHOULD BE USED AS A SEPARATOR BETWEEN THE GRADED STONE, THE SOIL BASE, AND THE ABUTMENTS. THE GEOTEXTILES WILL PREVENT THE MIGRATION OF SOIL PARTICLES FROM THE SUBGRADE INTO THE GRADED STONE. THE GEOTEXTILE SHALL BE SPECIFIED ON ACCORDANCE WITH AASHTO M288-96 SECTION 7.5, PERMANENT EROSION CONTROL RECOMMENDATIONS. THE GEOTEXTILE SHOULD BE PLACED IMMEDIATELY ADJACENT TO THE SUBGRADE WITHOUT ANY VOIDS.
MATERIALS
THE APRON MAY BE LINED WITH RIPRAP, GROUTED RIPRAP, OR CONCRETE. THE MEDIAN SIZED STONE FOR RIPRAP, D50, SHALL BE DETERMINED FROM THE CURVES, FIGURE 6-24.1 AND 6-24.2, ACCORDING TO THE TAILWATER CONDITION. THE GRADATION, QUALITY AND PLACEMENT OF RIPRAP SHALL CONFORM TO APPENDIX C.



PIPE OUTLET TO WELL-DEFINED CHANNEL: DESIGN SPECIFICATIONS TABLE

HW I.D.	D ₅₀	Q	V	L _s	W ₁	W ₂	d ₅₀	D
		(CFS)	(FPS)	(FT)	(FT)	(FT)	(IN.)	(IN.)
A-1								
B-1								

STORM DRAIN OUTLET PROTECTION
NOT TO SCALE

CONSTRUCTION SPECIFICATIONS:

- ENSURE THAT THE SUBGRADE FOR THE FILTER AND RIPRAP FOLLOWS THE REQUIRED LINES AND GRADES SHOWN IN THE PLAN. COMPACT ANY FILL REQUIRED IN THE SUBGRADE TO THE DENSITY OF THE SURROUNDING UNDISTURBED MATERIAL. LOW AREAS IN THE SUBGRADE ON UNDISTURBED SOIL MAY ALSO BE FILLED BY INCREASING THE RIPRAP THICKNESS.
- THE RIPRAP AND GRAVEL FILTER MUST CONFORM TO THE SPECIFIED GRADING LIMITS SHOWN ON THE PLANS.
- GEOTEXTILE MUST MEET DESIGN REQUIREMENTS AND BE PROPERLY PROTECTED FROM PUNCHING OR TEARING DURING INSTALLATION. REPAIR ANY DAMAGE BY REMOVING THE RIPRAP AND PLACING ANOTHER PIECE OF FILTER FABRIC OVER THE DAMAGED AREA. ALL CONNECTING JOINTS SHOULD OVERLAP A MINIMUM OF 1 FT. IF THE DAMAGE IS EXTENSIVE, REPLACE THE ENTIRE FILTER FABRIC.
- RIPRAP MAY BE PLACED BY EQUIPMENT, BUT TAKE CARE TO AVOID DAMAGING THE FILTER.
- THE MINIMUM THICKNESS OF THE RIPRAP SHOULD BE 1.5 TIMES THE MAXIMUM STONE DIAMETER.
- CONSTRUCT THE APRON ON ZERO GRADE WITH NO OVERFALL AT THE END. MAKE THE TOP OF THE RIPRAP AT THE DOWNSTREAM END LEVEL WITH THE RECEIVING AREA OR SLIGHTLY BELOW IT.
- ENSURE THAT THE APRON IS PROPERLY ALIGNED WITH THE RECEIVING STREAM AND PREFERABLY STRAIGHT THROUGHOUT ITS LENGTH. IF A CURVE IS NEEDED TO FIT SITE CONDITIONS, PLACE IT IN THE UPPER SECTION OF THE APRON.
- IMMEDIATELY AFTER CONSTRUCTION, STABILIZE ALL DISTURBED AREAS WITH VEGETATION.
- STONE QUALITY - SELECT STONE FOR RIPRAP FROM FIELD STONE OR QUARRY STONE. THE STONE SHOULD BE HARD, ANGULAR, AND HIGHLY WEATHER-RESISTANT. THE SPECIFIC GRAVITY OF THE INDIVIDUAL STONES SHOULD BE AT LEAST 2.5.
- FILTER - INSTALL A FILTER TO PREVENT SOIL MOVEMENT THROUGH THE OPENINGS IN THE RIPRAP. THE FILTER SHOULD CONSIST OF A GRADED GRAVEL LAYER OR A SYNTHETIC FILTER CLOTH. SEE APPENDIX C, P. C-1.

MAINTENANCE:
INSPECT RIPRAP OUTLET STRUCTURES AFTER HEAVY RAINS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE OR IF STONES HAVE BEEN DISLOADED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.

- NOTES:**
- LENGTH (L_o) IS THE RIPRAP LENGTH (AS SHOWN IN THE CHART).
 - DEPTH (D) IS THE RIPRAP DEPTH (1.5 TIMES THE MAXIMUM STONE DIAMETER, OR AS SHOWN ON DRAWINGS BUT NOT LESS THAN 12").
 - INSTALL A 6" MINIMUM DEEP FILTER STONE BLANKET (#57 STONE) OR FILTER FABRIC (AASHTO M288-96 SECTION 7.5) BETWEEN RIPRAP AND SOIL FOUNDATION.
 - IN A WELL-DEFINED CHANNEL, EXTEND THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TAILWATER DEPTH, OR TO THE TOP OF THE BANK, WHICHEVER IS LESS.
 - A FILTER BLANKET OR FILTER FABRIC SHOULD BE INSTALLED BETWEEN THE RIPRAP AND SOIL FOUNDATION.
 - FOR VELOCITIES UP TO 6.5 FPS, USE GDOT TYPE 3 WITH #57 FILTER BEDDING STONE.
 - FOR VELOCITIES OVER 6.5 FPS, CONSULT TABLE C-1.

TABLE C-1
GRADED RIP-RAP STONE

FLOW VELOCITY (FT./SEC.)	N.S.A. NO. ¹	SIZE INCHES (SQ. OPENING)			FILTER STONE N.S.A. NO. ¹
		MAX.	AVG. ²	MIN.	
2.5	R-1	1 1/2	3/4	No. 8	FS-1
4.5	R-2	3	1 1/2	1	FS-1
6.5	R-3	6	3	2	FS-2
9.0	R-4	12	6	3	FS-2
11.5	R-5	18	9	5	FS-2
13.0	R-6	24	12	7	FS-3
14.5	R-7	30	15	12	FS-3

TABLE C-2
FILTER BEDDING STONE

N.S.A. NO. ¹	SIZE INCHES (SQ. OPENING)		
	MAX.	AVG. ²	MIN. ³
FS-1	3/8	#30 MESH	#100 MESH
FS-2	2	#4	#100 MESH
FS-3	6 1/2	2 1/2	#16

TABLE C-4
FILTER BEDDING STONE

G.D.O.T. NO. ⁴	NOMINAL SIZE (INCHES)
3	2" - 1"
4	1 1/2" - 3/4"
5	1" - 1/2"
6	3/4" - 3/8"
57	1" - No. 4

TABLE C-3
GRADED RIP-RAP STONE

G.D.O.T. NO. ¹	SIZE INCHES (SQ. OPENING)			COMMON USES
	MAX.	AVG. ²	MIN. ³	
TYPE 3	12	9	5	CREAK BANKS, PIPE OUTLETS
TYPE 1	24	12	7	LAKES, SHORELINES, RIVERS

- NATIONAL STONE ASSOCIATION
- AT LEAST 50% OF THE INDIVIDUAL STONE PARTICLES MUST BE EQUAL OR LARGER THAN LISTED SIZE.
- 85-100% OF THE INDIVIDUAL STONE PARTICLES MAYBE LESS THAN LISTED SIZE.
- GEORGIA DEPARTMENT OF TRANSPORTATION

MULCHING ONLY

MULCHING BY ITSELF MAY BE USED AS TEMPORARY STABILIZATION (MULCHING ONLY) WHEN SEED WILL NOT HAVE A SUITABLE GROWING SEASON. STABILIZATION MAY BE ACCOMPLISHED WITH: STRAW - 2 TONS/ACRE OR HAY - 2.5 TONS/ACRE PROVIDED THAT THE APPROPRIATE DEPTH (2-4") IS ACHIEVED. ALL HAY OR STRAW SHALL BE ANCHORED WITH A TACKIFIER (Tb) (EMULSIFIED ASPHALT, GRADE AE-5 OR SS-1, AT A RATE OF 100 GAL. OF EMULSIFIED ASPHALT AND 100 GAL. OF WATER PER TON OF MULCH), AND PROVIDED THAT A CONTINUOUS COVERAGE OF 90% OR GREATER OF THE SOIL SURFACE IS MAINTAINED. OTHER ACCEPTABLE MULCHES ARE WOOD WASTE, BARK, OR SAWDUST SPREAD 2-3" DEEP. WHEN MULCH IS USED WITH SEED, FOLLOW THE SPECIFICATIONS FOR TEMPORARY SEEDING (Ds2) OR PERMANENT SEEDING (Ds3).

TEMPORARY AND PERMANENT GRASSING

- NOTES:**
- ALL SEEDING RATES ARE EXPRESSED AS PURE LIVE SEED (PLS).
 - MATTING BLANKETS (Mb) AND HYDROSEED ARE REQUIRED ON SLOPES STEEPER THAN 2H:1V.
 - THE LANDSCAPE PLANS, IF ANY WILL SUPERSEDE THIS DETAIL FOR PERMANENT VEGETATION.
 - MULCHING ONLY (Ds1) OR TEMPORARY GRASSING (Ds2) SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF DISTURBANCE AND WHEN ROUGH GRADED DISTURBANCE WILL LAST FOR LESS THAN SIX MONTHS. IF ROUGH GRADED AREAS WILL BE UNDISTURBED FOR LONGER THAN SIX MONTHS OR AREA IS AT FINAL GRADE, THEN PERMANENT VEGETATION (Ds3) SHALL BE USED.
 - BLOCK SOD (Ds4) PROVIDES IMMEDIATE COVER AND IS ESPECIALLY EFFECTIVE IN CONTROLLING EROSION ADJACENT TO CONCRETE FLUMES AND OTHER STRUCTURES.
 - THE CONTRACTOR SHALL SELECT A BMP SUITABLE TO THE SEASON OF THE YEAR AND THE GRADING STATUS OF THE AREA TO BE STABILIZED.
 - CONSTRUCTION SPECIFICATIONS FOR EACH BMP SHALL BE AS PUBLISHED IN THE MANUAL FOR SEDIMENT AND EROSION CONTROL IN GEORGIA, LATEST EDITION.

- SUBSTITUTE PENSACOLA BAHIA IN THE COASTAL MAJOR RESOURCE AREA OF GEORGIA.
- BERMUDA SHOULD NOT BE PLANTED IN THE M-L MAJOR RESOURCE AREA OF GEORGIA.
- MULCH FOR HYDROSEED
500 LB. OF WOOD CELLULOSE MULCH OR EQUIVALENT PER ACRE, THEN APPLY STRAW @ 2 TON/AC. OR HAY @ 2.5 TONS/AC. STRAW OR HAY SHALL BE DRY, NOT CAKED, AND FREE OF WEED SEED.
- SERICEA LESPEDEZA SHALL BE SCARIFIED AND INOCULATED WITH "EL" BACTERIA. USE DOUBLE THE RECOMMENDED RATE OF INOCULUM FOR CONVENTIONAL SEEDING AND 4X THE RECOMMENDED RATE FOR HYDROSEEDING. OTHERWISE FOLLOW THE SUPPLIER'S INSTRUCTIONS WHEN INOCULATING LEGUMES.

FERTILIZER SCHEDULE

TYPE OF SPECIES	YEAR	ANALYSIS OR EQUIVALENT N-P-K	RATE	N TOP DRESSING RATE
1. Cool season grasses	First	6-12-12	1500 lbs./ac.	50-100 lbs./ac. 1/2'
	Second	6-12-12	1000 lbs./ac.	30
	Maintenance	10-10-10	400 lbs./ac.	30
2. Cool season grasses and legumes	First	6-12-12	1500 lbs./ac.	0-50 lbs./ac. 1'
	Second	6-12-12	1000 lbs./ac.	—
	Maintenance	10-10-10	400 lbs./ac.	—
3. Ground covers	First	10-10-10	1300 lbs./ac. 3/4'	—
	Second	10-10-10	1000 lbs./ac. 3/4'	—
	Maintenance	10-10-10	1100 lbs./ac.	—
4. Pine seedlings	First	20-10-5	one 21-gram packet per seedling placed in the closing hole	—
	Maintenance	10-10-10	700 lbs./ac. 4'	—
5. Shrub Lespedeza	First	0-10-10	700 lbs./ac.	—
	Maintenance	10-10-10	700 lbs./ac. 4'	—
6. Temporary cover crops seeded alone	First	10-10-10	500 lbs./ac.	30 lbs./ac. 5'
	Maintenance	10-10-10	400 lbs./ac.	—
7. Warm season grasses	First	6-12-12	1500 lbs./ac.	50-100 lbs./ac. 2/6'
	Second	6-12-12	800 lbs./ac.	50-100 lbs./ac. 2'
	Maintenance	10-10-10	400 lbs./ac.	30 lbs./ac.
8. Warm season grasses and legumes	First	6-12-12	1500 lbs./ac.	50 lbs./ac. 6'
	Second	6-12-12	1000 lbs./ac.	—
	Maintenance	10-10-10	400 lbs./ac.	—

- 1/ Apply in spring following seeding.
- 2/ Apply in split applications when high rates are used.
- 3/ Apply in 3 split applications.
- 4/ Apply when plants are pruned.
- 5/ Apply to grass species only.
- 6/ Apply when plants grow to a height of 2 to 4 inches.





Figure 6-4.1
GaSWCC (Amended - 2009)

A-EC
50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE

EROSION CONTROL DETAILS



DATE	REVISIONS	DATE	REVISIONS

WILLO TRAIL - PHASE IV
ROSWELL, FULTON COUNTY, GEORGIA
PROPOSED PEDESTRIAN TRAIL
CONSTRUCTION PLANS

00:\GIS\909-2891\WILLO TRAIL Concept\Permitting\09-2891 Pl Gr-CDT Plans.dwg, 3/9/2010 8:45:40 AM, jlw, RFP Acad.pct, 1:1

Ds2 TEMPORARY GRASSING

TEMPORARY GRASSING SHALL CONSIST OF SOWING A QUICK GRASS SUCH AS RYE, BROWN TOP MILLET, OR A GRASS SUITABLE TO THE AREA AND SEASON. MULCH, LIME AND FERTILIZER MAY BE OMITTED UNLESS LOCAL CONDITIONS OR SOIL TESTS INDICATE OTHERWISE. TEMPORARY VEGETATIVE MEASURES SHOULD BE COORDINATED WITH PERMANENT MEASURES TO ASSURE ECONOMIC AND EFFECTIVE STABILIZATION. FOR ADDITIONAL OPTIONS OR IF THE AREA IS EXPECTED TO BE UNDISTURBED FOR LONGER THAN SIX MONTHS, PERMANENT PERENNIAL VEGETATION (Ds3) SHALL BE USED. REFER TO THE COMPANION PLANTING SCHEDULE UNDER PERMANENT GRASSING (Ds3).

Ds2 GRASSING SCHEDULE

Table 6-4.1 - Temporary Cover or Companion Crops 1/
PLANT, PLANTING RATES, AND PLANTING DATED FOR TEMPORARY COVER OR COMPANION CROPS 1/

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
BARLEY (Hordeum vulgare)																	14,000 seed per pound. Winterhardy. Use on productive soils.
alone	3 bu.	3.3 lb.															
in mixtures	12 bu. (24 lbs.)	0.6 lb.															
LESPEDeza ANNUAL (Lespedeza striata)																	200,000 seed per pound. May require several years. Use inoculant EL.
alone	40 lb.	0.9 lb.															
in mixtures	10 lb.	0.2 lb.															
LOVEGRASS WEEPING (Eragrostis curvula)																	1,200,000 seed per pound. May last for several years. Mix with Sorghum alopecuroides.
alone	4 lb.	0.1 lb.															
in mixtures	2 lb.	0.05 lb.															
MILLET BROWN TOP (Panicum brownianum)																	137,000 seed per pound. Quick dense cover. Will provide too much competition in mixture if sowed at high rates.
alone	40 lb.	0.9 lb.															
in mixtures	10 lb.	0.2 lb.															

Table 6-4.1 - Temporary Cover or Companion Crops 1/ - continued
PLANT, PLANTING RATES, AND PLANTING DATED FOR TEMPORARY COVER OR COMPANION CROPS 1/

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
MILLET PEARL (Pennisetum glaucum)																	88,000 seed per pound. Quick dense cover. May reach 8 feet in height. Not recommended for mixtures.
alone	50 lb.	1.1 lb.															
ORZ (Avena sativa)																	19,000 seed per pound. Use on productive soils. Not to winterhardy six yr or better.
alone	4 bu.	2.9 lb.															
in mixtures	1 bu. (2 lbs.)	0.7 lb.															
RYE (Secale cereale)																	19,000 seed per pound. Quick cover. Drought tolerant and winterhardy.
alone	3 bu.	3.9 lb.															
in mixture	1/2 bu. (28 lbs.)	0.6 lb.															
HYDRGRASS ANNUAL (Lolium temulentum)																	227,000 seed per pound. Dense cover. Very competitive and long to be used in mixtures.
alone	40 lb.	0.9 lb.															
SUDANGRASS (Sorghum sudanense)																	65,000 seed per pound. Good on droughty sites. Not recommended for mixtures.
alone	60 lb.	1.4 lb.															

Table 6-4.1 - Temporary Cover or Companion Crops 1/ - continued
PLANT, PLANTING RATES, AND PLANTING DATED FOR TEMPORARY COVER OR COMPANION CROPS 1/

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
TRITICALE (X-Triticosecale)																	Use on lower part of Southern Coastal Plain and in Atlantic Coastal Piedmont only.
alone	3 bu.	3.3 lb.															
in mixtures	12 bu. (24 lbs.)	0.6 lb.															
WHEAT (Triticum aestivum)																	15,000 seed per pound.
alone	3 bu.	4.1 lb.															
in mixtures	12 bu. (24 lbs.)	0.7 lb.															

1/ Temporary cover crops are very competitive and will crowd out perennials if seeded too heavily.
2/ Reduce seeding rates by 50% when drilled.
3/ PLS is an abbreviation for Pure Live Seed.
4/ M.L. represents the Mountain, Blue Ridge, and Ridges and Valleys M.L.R.s
P represents the Southern Piedmont M.L.R.A.
C represents the Southern Coastal Plain, Sand Hills, Black Lands, and Atlantic Coast Flatwoods M.L.R.s (See Figure 6-4.1, p. 6-10)

Ds3 PERMANENT GRASSING

PERMANENT GRASSING SHALL BE APPLIED AND REAPPLIED IF NECESSARY UNTIL FINAL STABILIZATION IS ACHIEVED. FINAL STABILIZATION MEANS THAT ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED, AND THAT FOR UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES, AT LEAST 70% OF THE SOIL SURFACE IS UNIFORMLY COVERED BY PERENNIAL VEGETATION WITHIN THE GROWING SEASON (OR OTHER EQUIVALENT PERMANENT STABILIZATION MEASURES). MULCHING IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER (25% UNCOVERED) WITHIN 24 HOURS AFTER SEEDING (3). REFER TO THE FERTILIZATION REQUIREMENTS CHART FOR TYPES AND RATES OF FERTILIZER APPLICATION.

Ds3 GRASSING SCHEDULE

Table 6-5.2 - Permanent Cover
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
BAHIA PENSACOLA (Paspalum notatum)																	160,000 seed per pound. Low growing. Slow forming. Slow to establish. Plant with a companion crop. Will spread into bermuda pastures and lawns. Mix with Sorghum alopecuroides or weeping lovegrass.
alone or with temporary cover	60 lb.	1.4 lb.															
with other perennials	30 lb.	0.7 lb.															
BAHIA WILMINGTON (Paspalum notatum)																	Same as above.
alone or with temporary cover	50 lb.	1.4 lb.															
with other perennials	30 lb.	0.7 lb.															
BERMUDA COMMON (Cynodon dactylon)																	1,787,000 seed per pound. Quick cover. Low growing and sod forming. Full sun. Good for athletic fields.
alone	10 lb.	0.2 lb.															
with other perennials	6 lb.	0.1 lb.															

Table 6-5.2 - Permanent Cover - continued
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
BERMUDA COMMON (Cynodon dactylon)																	Plant with winter annuals.
with temporary cover	10 lb.	0.2 lb.															
with other perennials	6 lb.	0.1 lb.															
BERMUDA SPRINGS (Cynodon dactylon)																	A cubic foot contains approximately 650 sprigs. A bushel contains 125 cubic feet or approximately 800 sprigs.
Coastal, Common, Midland, or TR 44	40 cu. ft. or sod plugs 3'x3'	0.9 cu. ft.															Same as above.
Coastal, Common, or TR 44																	
TR 78																	Southern Coastal Plain only.
CENTPEDE (Eranthis cicutoides)																	Drought tolerant. Full sun or partial shade. Effective against erosion and in compacted flow areas. Irrigation is needed until fully established. Do not plant near pastures. Winterhardy as far north as Athens and Atlanta.
Block sod only																	

Table 6-5.2 - Permanent Cover - continued
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
CROWN VETCH (Coronilla varia)																	100,000 seed per pound. Dense growth. Drought tolerant and fire resistant. Attractive rose, pink, and white blossoms spring to late fall. Mix with 30 pounds of tall fescue or 15 pounds of fine fescue seed with 10 inoculant. Use from North Atlanta and Northwest.
with winter annuals or cool season grasses	15 lb.	0.3 lb.															
FESCUE TALL (Festuca arvensis)																	227,000 seed per pound. Use alone only on better sites. Not for droughty soils. Mix with perennial ryegrass or crownvetch. Apply topdressing in spring following fall plantings. Not for heavy use areas or athletic fields.
alone	50 lb.	1.1 lb.															
with other perennials	30 lb.	0.7 lb.															
KUDZU (Pueraria thurberiana)																	Rapid and vigorous growth. Excellent in gully erosion control. Will climb. Good livestock forage.
plants or crowns	3' apart																

Table 6-5.2 - Permanent Cover - continued
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
LESPEDeza SERICEA (Lespedeza cuneata)																	350,000 seed per pound. Widely adapted. Low maintenance. Mix with weeping lovegrass, common bermuda, bahia, or tall fescue. Takes 2-3 years to become fully established. Excellent on acid soils. Inoculate seed with EL inoculant.
scarified	60 lb.	1.4 lb.															
unscarified	75 lb.	1.7 lb.															Mix with Tall fescue or winter annuals.
seed-bearing hay	3 tons	138 lb.															Cut when seed is mature, but before it shatters. Add Tall fescue or winter annuals.

Table 6-5.2 - Permanent Cover - continued
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
LESPEDeza AMBROVIGATA (Lespedeza virgata DC.)																	300,000 seed per pound. Height of growth is 18 to 24 inches. Adapted to urban areas. Spreading-type growth. Mix with bermuda, bahia, or tall fescue or winter annuals. Do not mix with Sorghum alopecuroides. Slow to develop seed stands. Inoculate seed with EL inoculant.
scarified	60 lb.	1.4 lb.															
unscarified	75 lb.	1.7 lb.															
LESPEDeza SHIRAZ (Lespedeza bicolor)																	Provides wildlife food and cover.
plants	3' x 7'																
LOVEGRASS WEEPING (Eragrostis curvula)																	1,500,000 seed per pound. Quick cover. Drought tolerant. Grows well with Sorghum alopecuroides on acid soils.
alone	4 lb.	0.1 lb.															
with other perennials	2 lb.	0.05 lb.															

Table 6-5.2 - Permanent Cover - continued
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

Species	Broadcast Rates 1/ - PLS 2/		Resource Area 3/	Planting Dates by Resource Areas												Remarks	
	Per Acre	Per 1000 sq. ft.		J	F	M	A	M	J	J	A	S	O	N	D		
MADEIRA (Panicum hamiltonianum)																	For very wet sites. May clog channels. Dig sprigs from local sources. Use along river banks and shorelines.
sofgrs	2' x 3' spacing																
PANICGRASS ATLANTIC COASTAL (Panicum amarum var. amarulum)																	Grows well on coastal sand dunes, borrow areas, and gravel pits. Provides winter cover for wildlife. Mix with Sorghum alopecuroides except on sand dunes.
alone	20 lb.	0.5 lb.															
with other perennials	10 lb.	0.25 lb.															
REED CANARY GRASS (Phalaris arundinacea)																	Grows similar to tall fescue.
alone	50 lb.	1.1 lb.															
with other perennials	30 lb.	0.7 lb.															
SARLLOWER AZTEC MAXIMILLIAM (Helianthus maximilianii)																	227,000 seed per pound. Mix with weeping lovegrass or other low-growing grasses or legumes.
alone	10 lb.	0.2 lb.															


1/ Reduce seeding rates by 50% when drilled.
2/ PLS is an abbreviation for Pure Live Seed. Refer to Section V.E. of these specifications.
3/ M.L. represents the Mountain, Blue Ridge, and Ridges and Valleys M.L.R.s
P represents the Southern Piedmont M.L.R.A.
C represents the Southern Coastal Plain, Sand Hills, Black Lands, and Atlantic Coast Flatwoods M.L.R.s (See Figure 6-4.1)

A-EC
50 Warm Springs Circle
Roswell, Georgia 30075
(770) 641-1942
www.aecat.com

LAND PLANNING
CIVIL ENGINEERING
LANDSCAPE ARCHITECTURE



EROSION CONTROL DETAILS



PERMANENT GRASSING SHRUB AND TREE COVERS

Table 6-5.3. Durable Shrubs and Ground Covers for Permanent Cover

Ground covers include a wide range of low-growing plants planted together in considerable numbers to cover large areas of the landscape. Ground covers grow slower than grasses. Weeds are likely to compete, especially the first year. Maintenance is needed to insure survival. These ground covers will not be used unless proper maintenance is planned. Maintain much at three-inch thickness until plants provide adequate cover.

Fall planting is encouraged because the need for constant watering is reduced and plants have time to establish new roots before hot weather.

Table with 5 columns: Common Name, Scientific Name, Mature Height, Plant Spacing, Comments. Lists plants like Abelia grandiflora, Gelsemium sempervirens, Ajuga reptans, etc.

GSWCC (Amended - 2009)

6-53

Table 6-5.3. Durable Shrubs and Ground Covers for Permanent Cover

Table with 5 columns: Common Name, Scientific Name, Mature Height, Plant Spacing, Comments. Lists plants like Repensens Holy, Andorra Juniper, Blue Chip Juniper, etc.

GSWCC (Amended - 2009)

6-54

Table 6-5.3. Durable Shrubs and Ground Covers for Permanent Cover

Table with 5 columns: Common Name, Scientific Name, Mature Height, Plant Spacing, Comments. Lists plants like Cherokee Rose, Memora Rose, St. Johnswort, etc.

GSWCC (Amended - 2009)

6-55

Table 6-5.4. Trees for Erosion Control

Table with 6 columns: SITE, SOIL MATERIAL, COMMON SOILS, TREE SPECIES 1/, SPACING, PLANTING DATES 2/. Lists sites like Borrow areas, Loamy, Clay, Streambanks.

1/Other trees and shrubs listed on Table 6-5.3 may be interplanted with the pines for improved wildlife benefits. 2/Type of Planting Tree Spacing No. of Trees Per Acre. 3/M-L represents the Mountains, Blue Ridge, and Ridges and Valleys MLRA. P represents the Southern Piedmont MLRA. C represents the Southern Coastal Plain, Sand Hills, Black Lands, and Atlantic Coast Flatwoods MLRAs (See Figure 6-4.1). 4/Fertilization of companion crop is ample for this species.

GSWCC (Amended - 2009)

6-56

Table 6-1.1. Unrooted Hardwood Cuttings - continued. Lists species like Acer rubrum, Thuja occidentalis, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-21

Table 6-1.1. Unrooted Hardwood Cuttings - continued. Lists species like Pinus strobus, Pinus taeda, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-22

Table 6-1.2. Native Plant Guide - continued. Lists species like Acer rubrum, Thuja occidentalis, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-23

Table 6-1.1. Unrooted Hardwood Cuttings - continued. Lists species like Ilex opaca, American Holly, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-25

Table 6-1.2. Native Plant Guide - continued. Lists species like Pinus taeda, Pinus strobus, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-26

Table 6-1.2. Native Plant Guide - continued. Lists species like Taxodium distichum, Taxus canadensis, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-27

Table 6-1.2. Native Plant Guide - continued. Lists species like Cornus sericea, Smilax latifolia, etc. with columns for Region, Stream Zone, Wildlife Value, Notes.

GSWCC (Amended - 2009)

6-24

AEC logo and contact information: 50 Warm Springs Circle, Roswell, Georgia 30075, (770) 641-1942, www.aecatd.com

Professional Engineer Seal for Georgia, No. 127178, GSWCC #5980, Exp. 3-11-2012

EROSION CONTROL DETAILS





Table with 2 columns: DATE, REVISIONS. Multiple empty rows for recording changes.

ROSWELL GEORGIA SINCE 1854 logo

WILLEO TRAIL - PHASE IV ROSWELL, FULTON COUNTY, GEORGIA PROPOSED PEDESTRIAN TRAIL CONSTRUCTION PLANS

STATE	SHEET NO.	TOTAL SHEETS
GA	55	




MAP INFO:

1. ROSWELL QUADRANGLE (1992, 20' CONTOUR INTERVALS)
2. SANDY SPRINGS QUADRANGLE (1997, 10' CONTOUR INTERVALS)
3. MOUNTAIN PARK QUADRANGLE (1992, 20' CONTOUR INTERVALS)

AEC
 50 Warm Springs Circle
 Roswell, Georgia 30075
 (770) 641-1942
 www.aecatd.com
 LAND PLANNING
 CIVIL ENGINEERING
 LANDSCAPE ARCHITECTURE



WATERSHED MAP



DATE	REVISIONS	DATE	REVISIONS



WILLEO TRAIL - PHASE IV
 ROSWELL, FULTON COUNTY, GEORGIA
 PROPOSED PEDESTRIAN TRAIL
 CONSTRUCTION PLANS

M:\2006\05\05-281 WILLEO TRAIL Concept Permitting\05-281 PR Ge-DOT Plans.dwg, 3/8/2010 8:56:49 AM, jw, MP Acad.pct, 1:1